TITLE SHEET AND INDEX

MARSTONS MILLS VILLAGE CENTER IMPROVEMENTS

IN THE TOWN OF

BARNSTABLE BARNSTABLE COUNTY


THE MASSACHUSETTS HIGHWAY DEPARTMENT STANDARD SPECIFICATIONS FOR HIGHWAYS AND DRAWINGS FOR SIGNS AND SUPPORTS, THE 1968 STANDARD DRAWINGS FOR TRAFFIC SIGNALS AND HIGHWAY LIGHTING AND THE LATEST EDITION OF THE AMERICAN STANDARD FOR NURSERY STOCK, WILL GOVERN.

INDEX

DESCRIPTION SHEET NO.


77-109 ----- CROSS SECTIONS 1 - 33

1	 TITLE SHEET AND INDEX
2	 LEGEND AND ABBREVIATIONS
3-4	 TYPICAL SECTIONS 1 - 2
5-14	 CONSTRUCTION NOTES AND DETAILS 1 - 10
15-22	 CONSTRUCTION PLANS 1 - 8
23-30	 DRAINAGE AND UTILITY PLANS 1 - 8
31-38	 PROFILES 1 - 8
39-46	 CURB TIE PLANS 1 - 8
47	 GRADING PLAN
48-55	 LANDSCAPE PLANS 1 - 8
56-63	 LIGHTING PLANS 1 - 8
64	 LIGHTING SCHEMATICS
65	 LIGHTING DETAILS
66-73	 TRAFFIC SIGNS AND PAVEMENT MARKING PLANS 1 - 8
74	 TRAFFIC SIGN SUMMARY
75-76	 TEMPORARY TRAFFIC CONTROL PLANS 1 - 2





FOR SHEETS 1-8, 15-22, 31-47, 66-109




FOR SHEETS



FOR SHEETS 9-14, 23-30,



FOR SHEETS (BOARDWALK DESIGN ONLY)



LENGTH OF PROJECT = 4209 FEET = 0.797 MILES

DESIGN DESIGNATION

ROUTE 149

25 MPH **DESIGN SPEED** 7,550 ADT (2013) 9,250 ADT (2033) 12% 50% NB / 50% SB T (AVERAGE DAY) 1,110

FUNCTIONAL CLASSIFICATION URBAN MINOR ARTERIAL

OCTOBER 2018

INCLUDES REVISIONS THROUGH 3-25-2019



350 MYLES STANDISH BLVD 14 BREAKNECK HILL RD SUITE 103 SUITE 201



LEGEND

GENERAL SYMBOLS

EXISTING PROPOSED JERSEY BARRIER ON BRIDGE OR JERSEY BARRIER CATCH BASIN 🔘 СВ T CI CI **CURB INLET** \bigoplus ⊕ BUOY BUOY FLAG POLE FLOW DIRECTION GAS PUMP □ DI DROP INLET • MAIL BOX ☐ GR ☐ GRAN POST GRANITE POST ☐ PLN PLANTER PLANTER POST O PST O POST TBH ☐ TBH TELEPHONE BOOTH O VLT VLT VAULT VALVE \otimes VLV \otimes VLV ⊕ WELL \oplus WELL WELL ELECTRIC MANHOLE (HANDHOLE) □ EHH O FCGA **GATE POST** —⊳ FL —⊳ FL FLOW LINE **GAS GATE BORING HOLE** MONITORING WELL TEP TEST PIT CONC. HDWL CONCRETE HEADWALL □ HH HANDHOLE HS STONE HEADWALL ♠ HYD HYDRANT LIGHT POLE **COUNTY BOUND** □ CO. BO. ☐ CO. BD. △ GPS **GPS POINT** ○ CMH CABLE MANHOLE DRAINAGE MANHOLE ELECTRIC MANHOLE GMH GAS MANHOLE ○ MMH MISC MANHOLE \bigcirc OMH OTHER MANHOLE SMH SEWER MANHOLE \bigcirc TMH TELEPHONE MANHOLE ○ WMH WATER MANHOLE \square MHB ■ MHB MHD BOUND ☐ MON MONUMENT ☐ MON □ SB ☐ SB STONE BOUND ■ TOWN OR CITY BD. TOWN OR CITY BOUND TRAVERSE OR TRIANGULATION STATION O TRNP TRANS. POLE –Ö– UFB UP WITH FIREBOX —Ö— UFB POLE WITH DOUBLE LIGHT Ф LPDL UP WITH 1 LIGHT _____ ULT \longrightarrow ULT **UTILITY POLE** ∪P UTILITY POLE WITH GUY 💮 BUSH BUSH TREE TREE O STUMP STUMP SWAMP / MARSH **WATER GATE** FIRE ALARM BOX PARKING METER PM ELECTRICAL GROUND **⋈** GV **GATE VALVE** RIP RAP **OVERHEAD CABLE** —·—· DIRECT BURIAL CABLE ———— CURBING —185 — CONTOURS **___**185**__** DRAIN PIPE (DOUBLE LINE 24 INCH AND OVER) ————— ELECTRIC DUCT " " ————— GAS MAIN " " ————s—— SEWER MAIN " " —— TELEPHONE DUCT " " ————— WATER MAIN " " BALANCE STONE WALL ∞ ⊨==== CULVERT ------ GUARD RAIL 0 0 0

— GUTTER LINE AT DRIVEWAYS

-x-x-x--x-- CHAIN LINK FENCE

GENERAL SYMBOLS (CONT.)

EXISTING	PROPOSED	_
	••••••	HAY BALES/SILT FENCE
		RETAINING WALL
		TREE LINE OR LIMIT OF CLEARING AND GRUBBING
		SAWCUT LINE
		TOP OR BOTTOM OF SLOPE
		LIMIT OF EDGE OF PAVEMENT OR COLD PLANE & OVERLAY
		LIMIT OF WORK
		BANK OF RIVER OR STREAM
<u>.</u> <u>₩F−#</u>		BORDER OF WETLAND
		100 FT WETLAND OR 200 FT RIVERFRONT BUFFER
		STATE HIGHWAY LAYOUT
		TOWN OR CITY LAYOUT
		COUNTY LAYOUT
		TOWN OR CITY BOUNDARY LINE
POR APPROX. P		PROPERTY LINE OR APPROXIMATE PROPERTY LINE
		• EASEMENT

PAVEMENT MARKINGS AND SIGNING SYMBOLS

 	/ 			
EXISTING	PROPOSED			
ONLY	PAVEMENT ARROW - WHITE LEGEND "ONLY" - WHITE	ONLY	Ε	
$\Delta\Delta\Delta\Delta$	STOP LINE - 12" - WHITE AAAA YIELD LINE			
	CW CROSSWALK			
	SWL SOLID WHITE LINE - 6"BWL BROKEN WHITE LINE - 6" (10' LINE, 30' SPACE)		0' L	LINE, 30' SPACE)
	YGL YELLOW GORE LINE - 12" (15' SPACING, 1:3 SLOPE DBYL DOUBLE YELLOW LINE - 6"		15' \$	' SPACING, 1:3 SLOPE)
	WGL WHITE GORE LINE - 12" SYL SOLID YELLOW LINE - 6"			
	 BYL — BROKEN YELLOW LINE - 6" (10' LINE, 30' SPACE) DWL DOTTED WHITE LINE - 6" (2' LINE, 6' SPACE) 		•	•
	- DYL DOTTED YELLOW LINE - 6" (2' LINE, 6' SPACE)	'ELLC	(2' l	' LINE, 6' SPACE)

ABBREVIATIONS

ANNUAL AVERAGE DAILY TRAFFIC

GENERAL

ABANDON

AADT

ABAN

HDW

HMA

HOR

HYD

JCT

M.A.

MAX

MB

MH

MIN

NB

NO.

PC

PGL

POC

POT

PRC

PROJ

PROP

PSB

MHB

HEADWALL

HYDRANT

JUNCTION

INVERT

HORIZONTAL

HOT MIX ASPHALT

TRUCK PERCENTAGE

MASSACHUSETTS HIGHWAY BOUND

POINT OF COMPOUND CURVATURE

POINT OF REVERSE CURVATURE

PLANTABLE SOIL BORROW

LENGTH OF CURVE

LEACHING BASIN

LIGHT POLE

MAST ARM

MAXIMUM

MAIL BOX

MANHOLE

MINIMUM

NUMBER

PROJECT

PROPOSED

NORTHBOUND

NOT IN CONTRACT

POINT OF CURVATURE

PROFILE GRADE LINE POINT OF INTERSECTION

POINT ON CURVE

POINT ON TANGENT

LEFT


BARNSTABLE MARSTONS MILLS VILLAGE CENTER IMPROVEMENTS


SHEET TOTAL SHEETS
2 109


LEGEND AND ABBREVIATIONS

GENERAL (CONT.)

ADAIN	ADAINDON	0511	TDAL (CONT.)
ADJ	ADJUST	GEN	ERAL (CONT.)
APPR	APPROVED		
APPROX	APPROXIMATE	PT	POINT OF TANGENCY
A.C.	ASPHALT CONCRETE	PVC	POINT OF VERTICAL CURVATURE
ACCM PIPE	ASPHALT COATED CORRUGATED METAL PIPE	PVI	POINT OF VERTICAL INTERSECTION
BIT	BITUMINOUS	PVT	POINT OF VERTICAL TANGENCY
		PVMT	PAVEMENT
BC	BOTTOM OF CURB		
BD	BOUND	PWW	PAVED WATER WAY
BL	BASELINE	PROP	PROPOSED
BLDG	BUILDING	R	RADIUS OF CURVATURE
BM	BENCH MARK	R&D	REMOVE AND DISPOSE
ВО	BY OTHERS	R&R	REMOVE AND RESET
BOS	BOTTOM OF SLOPE	RB	RECHARGE BASIN
BR	BRIDGE	RCP	REINFORCED CONCRETE PIPE
CB	CATCH BASIN	RD	ROAD
CBCI	CATCH BASIN WITH CURB INLET	RDWY	ROADWAY
			_
CC	CEMENT CONCRETE	REM	REMOVE
CCB	CAPE COD BERM	RET	RETAIN
CCM	CEMENT CONCRETE MASONRY	RET WALL	RETAINING WALL
CEM	CEMENT	ROW	RIGHT-OF-WAY
CI	CURB INLET	RR	RAILROAD
CIP	CAST IRON PIPE	R&R	REMOVE AND RESET
CIT	CHANGE IN TYPE	R&S	REMOVE AND STACK
CLF	CHAIN LINK FENCE	RT	RIGHT
CL	CENTERLINE	SB	SOUTHBOUND
CMP	CORRUGATED METAL PIPE		
	CORRUGATED METALT II E	SGC	SLOPED GRANITE CURB
CSP		SHLD	SHOULDER
CO	COUNTY	SHLO	STATE HIGHWAY LAYOUT LINE
CONC	CONCRETE	SMH	SEWER MANHOLE
CONT	CONTINUOUS	ST	STREET
CONST	CONSTRUCTION	STA	STATION
CR GR	CROWN GRADE	STNB	STONE BOUND
DHV	DESIGN HOURLY VOLUME	SW	SIDEWALK
DI	DROP INLET	T T	TANGENT DISTANCE OF CURVE/
DIA	DIAMETER	·	
DIP	DUCTILE IRON PIPE	TAN	TANGENT
DMH	DRAINAGE MANHOLE	TEMP	TEMPORARY
		TC	TOP OF CURB
DW	STEADY DON'T WALK - PORTLAND ORANGE	TLO	TOWN LAYOUT LINE
DWY	DRIVEWAY	TOS	TOP OF SLOPE
EA	EACH	TYP	TYPICAL
EB	EASTBOUND	UNK	UNKNOWN
ELEV (OR EL.)	ELEVATION	UP	UTILITY POLE
EMB	EMBANKMENT	VAR	VARIES
EOP	EDGE OF PAVEMENT	VAN	
EXIST	EXISTING		VERTICAL CURVE
EXC	EXCAVATION	VC	VERTICAL CURVE
F&C	FRAME AND COVER	VGC	VERTICAL GRANITE CURB
		WB	WESTBOUND
F&G	FRAME AND GRATE	WCR	WHEELCHAIR RAMP
FDN	FOUNDATION	WG	WATER GATE
FLDSTN	FIELDSTONE	WIP	WROUGHT IRON PIPE
GAR	GARAGE	WM	WATER METER/WATER MAIN
GD	GROUND	X-SECT	CROSS SECTION
GG	GAS GATE	A-OLU I	ONCOO OLOTION
GI	GUTTER INLET		
GIP	GALVANIZED IRON PIPE		
GRAN	GRANITE		
GRAV	GRAVEL		
GRD	GUARD		











- DETECTABLE WARNING PANELS SHALL BE INSTALLED ON ALL WHEELCHAIR RAMPS AND SHALL COMPLY WITH CONSTRUCTION STANDARD E 107.6.5. PAYMENT FOR DETECTABLE WARNING PANELS SHALL BE CONSIDERED INCIDENTAL TO THE CONSTRUCTION OF THE WHEELCHAIR RAMPS OR SIDEWALKS IN WHICH THEY ARE BEING INSTALLED. THE COLOR OF DETECTABLE WARNING PANELS SHALL BE AT THE DIRECTION OF THE TOWN.
- SEE SIGNS AND PAVEMENT MARKING PLANS FOR PROPOSED SIGNS AND DISPOSITION OF THE EXISTING SIGNS WITHIN THE PROJECT LIMITS OR AS DIRECTED BY THE TOWN.
- 8. DO NOT SCALE DRAWINGS UNLESS OTHERWISE NOTED. WRITTEN DIMENSIONS SHALL PREVAIL. REPORT ANY DISCREPANCIES TO THE ENGINEER IMMEDIATELY.
- 9. THE CONTRACTOR SHALL COMPLY WITH ALL APPLICABLE REGULATIONS OF THE OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA).
- 10. THE CONTRACTOR SHALL RESTORE ALL PUBLIC AND PRIVATE PROPERTY TO ITS PRE-CONSTRUCTION CONDITION AT NO ADDITIONAL COST TO THE TOWN.

^^^^^



CURB SETTING NOT TO SCALE



PROP 8" (MIN) └─ THICKNESS VARIES WITH THE RECLAIMED BASE COURSE -COURSE AND SLOPE OF EXIST SUBBASE TO REMAIN INTERMEDIATE COURSE TYPE A BERM

10'-0" 5'-0" RAISED CROSSING PVMT MARKING (TYP) (SEE DETAIL SHEET 8) 7% SLOPE MAX (TYP) -- STAMPED ASPHALT RUNNING BOND BRICK PATTERN 12" WHITE PVMT MARKINGS DETECTABLE WARNING PANEL

BARNSTABLE

MARSTONS MILLS VILLAGE CENTER IMPROVEMENTS

SHEET TOTAL NO. SHEETS

5 109

CONSTRUCTION NOTES AND DETAILS


SHEET 1 OF 10

DATE

11/28/18

REV#

BERM TYPE A NOT TO SCALE



STAMPED ASPHALT RUNNING BOND BRICK PATTERN - 2" SUPERPAVE SURFACE COURSE - 12.5 (SSC-12.5) 7% MAX SLOPE (TYP) 4.5" SUPERPAVE INTERMEDIATE COURSE - 19.0 (SIC-19.0 - 8" (MIN) RECLAIMED BASE COURSE 12" WHITE PVMT MARKINGS (TYP)

(FEDERAL YELLOW) (TYP)

RAISED CROSSWALK NOT TO SCALE


SECTION A-A

AT GRADE CROSSWALK NOT TO SCALE

BARNSTABLE MARSTONS MILLS VILLAGE CENTER IMPROVEMENTS

SHEET TOTAL SHEETS
6 109

CONSTRUCTION NOTES AND DETAILS SHEET 2 OF 10




- 1. OPERATION OF RRFB LED LIGHTS SHALL CONFORM TO FHWA INTERIM APPROVAL IA-21.
- 2. EACH RRFB UNIT SHALL CONTAIN A CONFIRMATION LIGHT WITHIN THE BEACON AT EACH END THAT SHALL BE ILLUMINATED WHEN THE RRFB UNIT IS ACTIVATED.
- 3. EACH RRFB UNIT SHALL BE SELF CONTAINED AND POWERED VIA A SOLAR
- 4. THE RRFB UNITS AT EACH CROSSWALK LOCATION SHALL COMMUNICATE WIRELESSLY WITH EACH OTHER. EACH CROSSWALK LOCATION SHALL OPERATE AS AN INDEPENDENT SYSTEM.
- 5. UPON ACTIVATION OF A WAITING PEDESTRIAN, RRFB UNITS SHALL FLASH SIMULTANEOUSLY FOR A PERIOD OF 15 SECONDS, THEN STOP FLASHING.
- RRFB UNITS SHALL BE TAPCO, INC BRAND OR APPROVED EQUAL.
 THE CONTRACTOR SHALL PERFORM A SOLAR SURVEY TO CONFIRM LOCATION ADEQUACY.


RECTANGULAR RAPID FLASHING BEACON (RRFB)

NOT TO SCALE

DWY#	 TYPE	MATERIAL	DRIVEWAY LOCATION		ROADWAY	TRANSITION LENGTH		
DVV 1 #	1111	MATERIAL	STATION	OFFSET	GUTTER SLOPE	LEFT SIDE	RIGHT SIDE	
1	1	CONC	104+74	11' RT	3.85%	14'-0"	6'-6"	
2	1	CONC	104+79	11' LT	3.85%	8'-0"	14'-0"	
3	1	CONC	105+41	11' RT	4.86%	15'-0"	6'-6"	
4	1	CONC	105+87	11' RT	2.86%	11'-0"	6'-6"	
5	1	CONC	106+58	11' RT	2.93%	6'-6"	11'-0"	
6	1	CONC	107+54	11' LT	0.42%	6'-6"	7'-8"	
7	1	CONC	108+53	11' RT	0.42%	7'-8"	6'-6"	
8	1	CONC	112+13	11' LT	1.20%	6'-6"	9'-0"	
9	1	CONC	112+80	11' LT	1.41%	6'-6"	9'-0"	
10	2	CONC	113+40	18'-4" LT	0.24%	6'-6"	7'-8"	
11	2	CONC	114+25	15'-6" LT	0.24%	6'-6"	7'-8"	
12	2	CONC	115+98	18'-0" LT	0.24%	6'-6"	7'-8"	
13	2	CONC	117+70	14'-6" LT	0.93%	6'-6"	7'-8"	
14	2	CONC	118+91	14'-6" LT	0.75%	6'-6"	7'-8"	
15	1	CONC	119+97	11' LT	1.15%	6'-6"	9'-0"	
16	1	CONC	120+19	11' RT	1.00%	6'-6"	-	
17	1	НМА	120+75	11' RT	1.00%	7'-8"	6'-6"	
18	1	НМА	121+18	11' LT	0.81%	6'-6"	7'-8"	
19	1	НМА	121+74	11' RT	1.01%	9'-0"	6'-6"	
20	1	НМА	121+84	11' LT	1.40%	9'-0"	6'-6"	
21	1	НМА	122+73	11' RT	1.64%	9'-0"	6'-6"	
22	1	НМА	123+12	11' RT	1.82%	3'-3" **	11'-0"	
23	1	НМА	123+55	11' LT	1.82%	9'-0"	6'-6"	
24	1	НМА	123+57	11' LT	2.08%	6'-6"	11'-0"	
25	1	НМА	124+07	11' LT	2.08%	6'-6"	11'-0"	
26	1	НМА	124+20	11' RT	2.04%	11'-0"	6'-6"	
27	1	CONC	201+42	11' RT	6.67%	15'-0"	6'-6"	
28	1	CONC	202+32	11' RT	4.35%	15'-0"	6'-6"	
29	1	CONC	203+65	11' RT	5.56%	15'-0"	6'-6"	
30	1	НМА	205+09	11' LT	2.04%	3'-3" **	11'-0"	
31	1	НМА	205+85	11' LT	1.20%	-	9'-0"	
32	1	НМА	205+99	11' RT	1.20%	-	6'-6"	
33	1	НМА	206+14	11' RT	1.20%	9'-0"	-	
34	1	НМА	206+37	11' LT	1.20%	6'-6"	9'-0"	
35	1	НМА	207+42	11' RT	1.20%	9'-0"	6'-6"	
36	1	НМА	207+51	11' LT	1.20%	6'-6"	-	
37	1	НМА	207+78	11' LT	1.20%	-	9'-0"	
38	1	НМА	208+55	11' RT	1.20%	9'-0"	6'-6"	
39	1	НМА	209+79	11' LT	1.20%	9'-0"	6'-6"	
40	1	CONC	300+54	12'-4" LT	1.20%	6'-6"	9'-0"	
41	1	НМА	302+50	11' LT	5.50%	6'-6"	7'-8"	
42	1	HMA	302+87	11' LT	5.36%	10'-2"	15'-0"	


** 3 INCH REVEAL






* TOLERANCE FOR CONSTRUCTION = ±0.5%

DRIVEWAY TYPE 1 NOT TO SCALE





* TOLERANCE FOR CONSTRUCTION = ±0.5%

SECTION A-A

DRIVEWAY TYPE 2


NOT TO SCALE





SHEET TOTAL SHEETS
7 109

CONSTRUCTION NOTES AND DETAILS SHEET 3 OF 10

REV#	DATE
\triangle	11/28/18







* TOLERANCE FOR CONSTRUCTION = ±0.5%

	LIMIT OF CEMENT C	ONCRETE RAMP	1
OIDEMALK	RAMP LENGTH	LEVEL LANDING	
SIDEWALK	7.5%*	1.5%*	ROADWAY
4" CEM CONC			
8" GRAVEL BORROW (TYPE b)			
	SECTION	<u> </u>	

* TOLERANCE FOR CONSTRUCTION = ±0.5%


WCR#		CHAIR RAMP CATION	ROADWAY GUTTER	TRANSITIO	ON LENGTH
WCR#	STATION	OFFSET	SLOPE	LEFT SIDE	RIGHT SIDE
3	110+42	11 LT	1.00%	4'-4"	7'-8"
5	115+74	11 RT	0.45%	3'-6" **	
8	124+78	11 RT	2.40%	5'-6" **	6'-6"
9	124+78	11 LT	2.59%	6'-6"	7'-8"
10	124+97	23 RT	3.80%		5'-0" **
11	125+41	23 RT	3.80%	7'-0"	
13	200+14	15 RT	4.80%	15'-0"	6'-6"
16	204+71	11 LT	3.56%	3'-3" **	7'-6" **
17	204+71	11 RT	2.16%	15'-0"	6'-6"
20	300+18	22 LT	1.37%	9'-0"	6'-6"
21	300+27	18 RT	1.37%		7'-6"

** 3 INCH REVEAL

WHEELCHAIR RAMP TYPE 1
NOT TO SCALE

WCR#	_	HAIR RAMP ATION	ROADWAY GUTTER	TRANSITION	
	STATION	OFFSET	SLOPE	LENGTH	
1	107+36	11 RT	2.60%	11'-0"	
2	107+79	11 RT	0.60%	7'-11"	
4	115+74	10 LT	0.08%	7'-6"	
6	116+25	20 RT	6.57%	6'-6"	
7	116+60	20 RT	0.57%	7'-0"	
12	125+56	66 LT	4.80%	15'-0"	
14	200+47	12 RT	1.90%	9'-0"	
15	200+77	13 RT	4.50%	15'-0"	
18	210+53	12 RT	0.16%	8'-0"	
19	211+02	12 RT	1.83%	9'-0"	
24	305+76	11 LT	2.79%	6'-6"	

WHEELCHAIR RAMP TYPE 2 NOT TO SCALE



NOTES:

2" x 6" x 18" LONG SPRUCE

- 1. LUMBER TO BE PLANED ON ALL FOUR SIDES TO FULL 2"X6" SIZE TO FIT BOTTOM OF MAIL BOXES.
- 2. TO SET $1\frac{1}{2}$ " GALVANIZED PIPE POST, USE DRIVING POINT OF SAME SIZE, THEN TAMP POST INTO PLACES SO AS TO BE PLUMB BOTH WAYS.
- 3. ALL FITTINGS (PIPE FLANGES, PIPE, SCREWS, NAILS, ETC) ARE TO BE GALVANIZED.
- 4. FOR ALL DESCRIPTIONS, MATERIALS, AND CONSTRUCTION METHODS SEE STANDARD SPECIFICATIONS.
- 5. A 4"X4" PRESSURE TREATED WOOD POST MAY SUBSTITUTED FOR A PIPE POST.


6. EXISTING MAILBOXES WILL BE RESET UNLESS RESIDENTS PROVIDE A DIFFERENT MAILBOX TO RESET, AND RESIDENTS WILL BE PROVIDED THEIR CHOICE OF PIPE OR LUMBER POST.

RURAL MAILBOX


NOT TO SCALE

* TOLERANCE FOR CONSTRUCTION = ±0.5%

ON-STREET HANDICAP PARKING DETAIL NOT TO SCALE




ON-STREET PARKING DETAIL NOT TO SCALE



- SIGN POST 2-2'X2' - CONCRETE OR BITUMINOUS CONCRETE SURFACE - ANCHOR SLEEVE 2-2'X2' - HOLE DIAMETER 00000 - SIGN POST ANCHOR 2'X2'

P-5 TELESCOPIC TUBULAR POST NOT TO SCALE




NOTES:
1. SYMBOL SHALL BE CENTERED IN THE PARKING STALL.
2. PAVEMENT MARKINGS TO BE INSTALLED IN LOCATIONS SHOWN ON THE PLANS.

HANDICAP PARKING SYMBOL NOT TO SCALE


BARNSTABLE MARSTONS MILLS VILLAGE CENTER IMPROVEMENTS

SHEET TOTAL SHEETS 8 109


CONSTRUCTION NOTES AND DETAILS SHEET 4 OF 10




"SLOW" PAVEMENT MARKING NOT TO SCALE



RAISED CROSSING PAVEMENT MARKING NOT TO SCALE



SHARROW SYMBOL NOT TO SCALE



YIELD LINE NOT TO SCALE

CASH MARKET (105 ROUTE 149) PARKING AREA DETAIL NOT TO SCALE

THIS DOES NOT CONSTITUTE A GUARANTEE THAT NO SUCH EASEMENTS EXIST.

THE ELEVATIONS DEPICTED HEREON WERE BASED ON THE NORTH AMERICAN VERTICAL DATUM OF 1988.

TOTAL CONTOUR INTERVAL OF FOUR TO ONE FOOT

ALL ABUTTING PROPERTY AND BOUNDARY LINES DEPICTED ARE APPROXIMATE ONLY

THE ACCURACY OF MEASURED PIPE INVERTS AND PIPE SIZES IS SUBJECT TO FIELD CONDITIONS, THE ABILITY TO MAKE VISUAL OBSERVATIONS, DIRECT ACCESS TO THE VARIOUS ELEMENTS AND OTHER

GENERAL CONSTRUCTION NOTES

DEEDS OBTAINED FROM THE PUBLIC RECORDS.

- ALL WORK TO COMPLETE THIS PROJECT AS INDICATED ON THE DRAWINGS AND IN THE SPECIFICATIONS IS 4. PROTECT THE ADJACENT RESOURCE AREA FROM SEDIMENTATION DURING PROJECT CONSTRUCTION
- MAKE ALL NECESSARY CONSTRUCTION NOTIFICATIONS AND APPLY FOR AND OBTAIN ALL NECESSARY CONSTRUCTION PERMITS, PAY ALL FEES INCLUDING POLICE DETAILS AND POST ALL BONDS, IF NECESSARY, ASSOCIATED WITH THE SAME, AND COORDINATE WITH THE OWNER AND THE ENGINEER.
- ALL EXISTING CONDITIONS SHOWN ARE APPROXIMATE AND ARE BASED ON THE BEST INFORMATION AVAILABLE. PRIOR TO THE START CONSTRUCTION VERIFY THAT THE PROPOSED IMPROVEMENTS SHOWN ON THE PLANS DO NOT CONFLICT WITH ANY KNOWN EXISTING OR OTHER PROPOSED IMPROVEMENTS. IF ANY CONFLICTS ARE DISCOVERED, NOTIFY THE OWNER AND THE ENGINEER PRIOR TO INSTALLING ANY PORTION OF THE SITE WORK WHICH WOULD BE AFFECTED.
- THE LOCATION AND/OR ELEVATION OF EXISTING UTILITIES AND STRUCTURES AS INDICATED ON THE DRAWINGS ARE BASED ON RECORDS OF VARIOUS UTILITY COMPANIES. AND WHEREVER POSSIBLE MEASUREMENTS TAKEN IN THE FIELD. THIS INFORMATION IS NOT TO BE RELIED UPON AS BEING EXACT OR COMPLETE. VERIFY THE LOCATION OF ALL UNDERGROUND UTILITIES AND STRUCTURES IN THE FIELD PRIOR TO THE START OF CONSTRUCTION. CONTACT THE APPROPRIATE UTILITY COMPANY, ANY GOVERNING PERMITTING AUTHORITY IN THE TOWN, AND "DIGSAFF" (1-888-344-7233) AT LEAST 72 HOURS. PRIOR TO ANY EXCAVATION WORK IN PREVIOUSLY UNALTERED AREAS TO REQUEST EXACT FIELD LOCATION OF UTILITIES. THE CONTRACTOR MUST RESOLVE CONFLICTS BETWEEN THE PROPOSED IMMEDIATELY. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR DAMAGES INCURRED AS A RESULT OF SURFACE OF SOIL STOCKPILES WITH SILT SOCK, SILT FENCE, STRAWBALES, OR A UTILITIES AND FIELD-LOCATED UTILITIES AND REPORT ANY DISCREPANCIES TO THE ENGINEER UTILITIES OMITTED, INCOMPLETELY OR INACCURATELY SHOWN. THE CONTRACTOR MUST MAINTAIN ACCURATE RECORDS OF THE LOCATION AND ELEVATION OF ALL WORK INSTALLED AND EXISTING UTILITIES FOUND DURING CONSTRUCTION FOR THE PREPARATION OF THE AS-BUILT PLAN.
- COORDINATE AND MAKE ALL CONNECTION ARRANGEMENTS WITH UTILITY COMPANIES. AS REQUIRED.
- THE CONTRACTOR MUST MAINTAIN ALL EXISTING UTILITIES IN WORKING ORDER AND FREE FROM DAMAGE DURING THE ENTIRE DURATION OF THE PROJECT. REPAIR ANY DAMAGE TO EXISTING UTILITY LINES OR STRUCTURES INCURRED DURING CONSTRUCTION OPERATIONS AT NO COST TO THE OWNER. THE CONTRACTOR IS RESPONSIBLE FOR ALL COST RELATED TO THE REPAIR OF UTILITIES. EXCAVATION REQUIRED WITHIN THE PROXIMITY OF EXISTING UTILITY LINES MUST BE DONE BY HAND.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR ADJUSTING OR REMOLDING ALL DRAINAGE, WATER, SEWER, OR GAS STRUCTURES WITHIN THE PROJECT LIMITS AS DIRECTED BY THE TOWN.

- THE CONTRACTOR SHALL NOT STORE ANY APPARATUS, MATERIALS, SUPPLIES, OR EQUIPMENT ON DRAINAGE STRUCTURES, PRIVATE PROPERTY OR WITHIN 100 FEET OF WETLANDS, UNLESS INDICATED ON
- THE CONTRACTOR SHALL PERFORM TEST PITS AT LOCATIONS WHERE DIRECTED BY THE TOWN AND OR ENGINEER

CONTRACTOR IS RESPONSIBLE FOR ALL TRENCH SAFETY INCLUDING ANY LOCAL AND/OR STATE PERMITS REQUIRED FOR THE TRENCH WORK. IF THIS WORK IS REQUIRED TO OCCUR OUTSIDE THE AGREED UPON HOURS OF OPERATION FOR THE FACILITY, THE CONTRACTOR MUST PLAN ACCORDINGLY.

INSTALL ALL UTILITY TRENCH WORK PRIOR TO INSTALLING NEW PAVEMENT AS INDICATED ON THE DRAWINGS.

ALL STRUCTURES AND PIPELINES LOCATED ADJACENT TO THE TRENCH EXCAVATION SHALL BE

- PROTECTED AND FIRMLY SUPPORTED BY THE CONTRACTOR UNTIL THE TRENCH IS BACKFILLED.INJURY 1 ANY SUCH STRUCTURE CAUSED BY, OR RESULTING FROM, THE CONTRACTOR'S OPERATIONS SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE. ALL UTILITIES REQUIRING REPAIR, RELOCATION OR ADJUSTMENT AS A RESULT OF THE PROJECT SHALL BE COORDINATED THROUGH THE RESPECTIVE UTILITY AND THE TOWN
- IN THOSE INSTANCES WHERE POWER OR TELEPHONE POLE SUPPORT IS REQUIRED, THE CONTRACTOR SHALL PROVIDE A MINIMUM 48-HOUR NOTIFICATION TO THE RESPECTIVE UTILITY COMPANY. NO ADDITIONAL PAYMENT WILL BE PROVIDED FOR TEMPORARY BRACING OF UTILITIES.
- THE CONTRACTOR IS TO TAKE SPECIAL CARE NOT TO DAMAGE TREES, BUSHES, PLANTS, FLOWERS, STONEWALLS, FENCES, ETC. WITHIN THE CONSTRUCTION AREA UNLESS THEY ARE NOTED TO BE REMOVED. CONTRACTOR SHALL REPLACE AT NO COST TO OWNER, ALL DAMAGED ITEMS.
- CONTRACTOR SHALL REMOVE AND REPLACE, OR REPAIR, ALL CURBS, SIDEWALKS, PAVEMENT AND OTHER ITEMS DAMAGED BY HIS CONSTRUCTION ACTIVITIES TO AT LEAST THEIR ORIGINAL CONDITION, AND TO THE SATISFACTION OF THE TOWN AND ENGINEER.
- THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE A TELEPHONE NUMBER WHERE THE CONTRACTOR CAN BE REACHED 24 HOURS A DAY, 7 DAYS A WEEK.
- THE LOCATION AND LIMITS OF ALL ON-SITE WORK AND STORAGE AREAS SHALL BE REVIEWED/COORDINATED WITH, AND ACCEPTABLE TO THE TOWN. THE CONTRACTOR SHALL LIMIT **ACTIVITIES TO THESE AREAS**
- THE CONTRACTOR SHALL BE REQUIRED TO TEMPORARILY PAVE ALL DISTURBED TRAVEL WAYS, SIDEWALKS & DRIVEWAYS NOT UNDER CONSTRUCTION OR IF LEFT DURING NON WORKING HOURS AND AS REQUIRED BY THE TOWN

9. IMPORT ONLY CLEAN MATERIAL. MATERIAL FROM AN EXISTING OR FORMER 21E SITE AS DEFINED BY THE MASSACHUSETTS CONTINGENCY PLAN 310 CMR 40.0000 WILL NOT BE ACCEPTED

). IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO ESTABLISH AND MAINTAIN ALL CONTROL POINTS AND BENCHMARKS DURING CONSTRUCTION INCLUDING BENCHMARK LOCATIONS AND ELEVATIONS AT CRITICAL AREAS. COORDINATE WITH THE ENGINEER THE LOCATION OF ALL CONTROL POINTS AND BENCHMARKS

. SITE LAYOUT SURVEY REQUIRED FOR CONSTRUCTION MUST BE PROVIDED BY THE CONTRACTOR AND

- PERFORMED BY A MASSACHUSETTS' REGISTERED PROFESSIONAL LAND SURVEYOR. THE CONTRACTOR RESPONSIBLE FOR COORDINATING WITH THE SURVEYOR FOR ALL SITE SURVEY WORK.
- . MAINTAIN ALL GRADE STAKES SET BY THE SURVEYOR. GRADE STAKES ARE TO REMAIN UNTIL A FINAL INSPECTION OF THE ITEM HAS BEEN COMPLETED BY THE ENGINEER. RE-STAKING OF PREVIOUSLY SURVEYED SITE FEATURES IS THE RESPONSIBILITY (INCLUDING COST) OF THE CONTRACTOR.
- 23. PROVIDE ALL CONSTRUCTION SERVICE IN ACCORDANCE WITH APPLICABLE LAWS AND REGULATIONS REGARDING NOISE, VIBRATION, DUST, SEDIMENTATION CONTAINMENT, AND TRENCH WORK.
- 24. COLLECT SOLID WASTES AND STORE IN A SECURED DUMPSTER. THE DUMPSTER MUST MEET ALL LOCAL AND STATE SOLID WASTE MANAGEMENT REGULATIONS.
- . REGULARLY INSPECT THE PERIMETER OF THE PROPERTY TO CLEAN UP AND REMOVE LOOSE CONSTRUCTION DEBRIS BEFORE IT LEAVES THE SITE. PROMPTLY REMOVE ALL DEMOLITION DEBRIS FROM THE SITE TO AN APPROVED DUMP SITE.
- 26. ALL TRUCKS LEAVING THE SITE MUST BE COVERED.
- 27. DO NOT WASH ANY CONCRETE TRUCKS ONSITE. REMOVE BY HAND ANY CEMENT OR CONCRETE DEBRIS LEFT IN THE DISTURBED AREA.
- 28. BURIAL OF ANY STUMPS, SOLID DEBRIS, AND/OR STONES/BOULDERS ONSITE IS PROHIBITED.
- 29 IMMEDIATELY CONTACT AND COORDINATE WITH THE ENGINEER AND OWNER IF ANY DEVIATION OR ALTERATION OF THE WORK PROPOSED ON THESE DRAWINGS IS REQUIRED.
-). AT THE END OF CONSTRUCTION, REMOVE ALL CONSTRUCTION DEBRIS AND SURPLUS MATERIALS FROM THE SITE PERFORM A THOROUGH INSPECTION OF THE WORK PERIMETER. COLLECT AND REMOVE ALL MATERIALS AND BLOWN OR WATER CARRIED DEBRIS FROM THE SITE.

EROSION & SEDIMENT CONTROL (ESC) NOTES

1. PRIOR TO THE START OF CONSTRUCTION A NOTICE OF INTENT (NOI) MUST BE FILED WITH NPDES. REFER TO THE STORMWATER AND POLLUTION PREVENTION PLAN (SWPPP) REGARDING ALL EROSION CONTROL MATTERS. MAINTAIN A WORKING COPY OF THE SWPPP ONSITE AT ALL TIMES. FOLLOW THE SWPPP PROTOCOL FOR SITE MAINTENANCE, INSPECTIONS AND PROPER DOCUMENTATION UNTIL THE SITE HAS BEEN ACCEPTED BY THE OWNER. AT THE COMPLETION OF THE PROJECT THE CONTRACTOR OR OWNER MUST FILE A NOTICE OF TERMINATION WITH NPDES. IN ACCORDANCE WITH NPDES REGULATIONS, THE COMPLETED SWPPP MUST INCLUDE ALL OF THE SITE EROSION CONTROL DOCUMENTATION, WEEKLY EROSION INSPECTION REPORTS COMPLETED BY THE DESIGNATED SITE PERSONNEL, AND ANY OTHER PERTINENT SITE DOCUMENTATION MUST BE RETAINED FOR A MINIMUM OF 3 YEARS FROM THE DATE OF

DESIGNATE ON-SITE PERSONNEL RESPONSIBLE FOR THE DAILY INSPECTION AND MAINTENANCE OF ALL SEDIMENT AND EROSION CONTROLS AND IMPLEMENTATION OF ALL NECESSARY MEASURES TO CONTROL EROSION AND PREVENT SEDIMENT FROM LEAVING THE SITE

INSTALL ALL EROSION AND SEDIMENT CONTROL (ESC) MEASURES AS INDICATED ON DRAWINGS IN CONSULTATION WITH THE CONSERVATION AGENT, AND ENGINEER BEFORE ANY CONSTRUCTION CTIVITIES BEGIN. INSPECT. MAINTAIN. REPAIR AND REPLACE EROSION CONTROL MEASURES. A NECESSARY, DURING THE ENTIRE CONSTRUCTION PERIOD OF THE PROJECT. THE SITE PERIMETER EROSION CONTROLS ARE THE DESIGNATED LIMIT OF WORK. INFORM ALL PERSONNEL WORKING ON THE PROJECT SITE THAT NO CONSTRUCTION ACTIVITY IS TO OCCUR BEYOND THE LIMIT OF WORK AT ANY TIME THROUGHOUT THE CONSTRUCTION PERIOD

UNTIL ACCEPTANCE BY THE OWNER & IN CONFORMANCE WITH THE ORDER OF CONDITIONS.

KEEP THE LIMIT OF CLEARING, GRADING AND DISTURBANCES TO A MINIMUM WITHIN THE PROPOSED AREA OF CONSTRUCTION. PHASE THE SITE WORK IN A MANNER TO MINIMIZE AREAS OF EXPOSED SOIL. IF TREES ARE TO BE CUT, CLEAR AND GRUB ONLY THOSE AREAS WHICH ARE ACTIVELY UNDER CONSTRUCTION. PROPERLY INSTALL THE SEDIMENTATION CONTROLS PRIOR TO BEGINNING ANY LAND CLEARING ACTIVITY AND/OR OTHER CONSTRUCTION RELATED WORK

MONITOR LOCAL WEATHER REPORTS DURING CONSTRUCTION AND PRIOR TO SCHEDULING EARTHMOVING OR OTHER CONSTRUCTION ACTIVITIES WHICH LEAVE LARGE DISTURBED AREAS UNSTABILIZED. IF INCLEMENT WEATHER IS PREDICTED. USE BEST PROFESSIONAL JUDGEMENT AND GOOD CONSTRUCTION PRACTICES WHEN SCHEDULING CONSTRUCTION ACTIVITIES AND ENSURE THE NECESSARY EROSION CONTROL DEVICES ARE INSTALLED AND FUNCTIONING PROPERLY TO MINIMIZE EROSION FROM ANY IMPENDING WEATHER EVENTS

INSPECT EROSION AND SEDIMENT CONTROL DEVICES AND STABILIZED SLOPES ON A WEEKLY BASIS AND AFTER EACH RAINFALL EVENT OF .25 INCH OR GREATER. REPAIR IDENTIFIED PROBLEMS WITHIN 24 HOURS TO ENSURE EROSION AND SEDIMENT CONTROLS ARE IN GOOD WORKING ORDER. RESET OR REPLACE MATERIALS AS REQUIRED

COMBINATION OF SILT FENCE WITH STRAWBALE, AS DETERMINED NECESSARY.

9. DISTURBED AREAS AND SLOPES MUST NOT BE LEFT UNATTENDED OR EXPOSED FOR EXCESSIVE PERIODS OF TIME SLICH AS THE INACTIVE WINTER SEASON PROVIDE APPROPRIATE STABILIZATION PRACTICES ON ALL DISTURBED AREAS AS SOON AS POSSIBLE BUT NOT MORE THAN 14 DAYS AFTER THE CONSTRUCTION ACTIVITY IN THAT AREA HAS TEMPORARILY OR PERMANENTLY CEASED. REINFORCE TEMPORARY AREAS HAVING A SLOPE GREATER THAN 4:1 WITH EROSION BLANKETS OR APPROVED EQUAL UNTIL THE SITE IS PROPERLY STABILIZED. TEMPORARY SWALES MAY ALSO BE REQUIRED IF DETERMINED NECESSARY IN THE FIELD BY THE ENGINEER.

INSTALL A CATCH BASIN INSERT OR APPROVED EQUIVALENT IN EACH EXISTING CATCH BASIN RECEIVING RUNOFF FROM THE SITE. UPON THE INSTALL ATION OF FACH CATCH BASIN, INSTALL AN INSERT OR APPROVED EQUIVALENT. INSPECT SILT SACKS, AFTER EACH SIGNIFICANT STORM EVENT AND REMOVE AND EMPTY AS NEEDED FOR THE DURATION OF THE CONSTRUCTION PERIOD

SMALL SEDIMENTATION BASINS MAY BE CONSTRUCTED ON AN AS-NEEDED BASIS DURING CONSTRUCTION TO AID IN THE CAPTURE OF SITE RUNOFF AND SEDIMENT. IT WILL BE THE RESPONSIBILITY OF THE SITE CONTRACTOR, IN CONSULTATION WITH THE ENGINEER, TO SIZE AND CREATE THESE BASINS IN APPROPRIATE LOCATIONS.

CONTAIN ALL SEDIMENT ON SITE. SWEEP ALL EXITS FROM THE SITE AS NECESSARY INCLUDING ANY SEDIMENT TRACKING. SWEEP PAVED AREAS AS NEEDED TO REMOVE SEDIMENT AND POTENTIAL POLLUTANTS ACCUMULATED DURING SITE CONSTRUCTION.

REMOVE ACCUMULATED SEDIMENT FROM ALL TEMPORARY PRACTICES AND DISPOSE OF IN A PRE-APPROVED LOCATION.

14. TO ENSURE ALL EROSION AND SEDIMENTATION CONTROL DEVICES ARE PROPERLY MAINTAINED AND REPAIRED IN A TIMELY AND RESPONSIBLE MANNER, PROVIDE ON SITE, OR MAKE READILY AVAILABLE, THE NECESSARY EQUIPMENT AND SITE PERSONNEL DURING CONSTRUCTION HOURS FOR THE DURATION OF THE PROJECT. IF SITE WORK IS SUSPENDED DURING THE WINTER MONTHS THE CONTRACTOR MUST CONTINUE TO PROVIDE PERSONNEL AND EQUIPMENT ON SITE OR READILY AVAILABLE

PRIOR TO THE INSTALLATION OF FILTER FABRIC AND MEDIA WITHIN THE BIORETENTION AREAS. REMOVE AND PROPERLY DISPOSE OF SEDIMENT ACCUMULATED IN ANY PARTIALLY CONSTRUCTED OR TEMPORARY BIORETENTION/DRAINAGE AREA USED FOR SEDIMENT CONTROL DURING CONSTRUCTION. PROVIDE A SURFACE FLEVATION AT A MINIMUM 1-FOOT AROVE THE ROTTOM OF MEDIA FLEVATION AS SHOWN IN THE BIORETENTION SCHEDULE FOR PARTIALLY CONSTRUCTED BIORETENTION AREAS. THIS ALLOWS FOR AN OVER-DIG OF THE COLLECTED SEDIMENT FROM WITHIN THE BIORETENTION AREA PRIOR TO MEDIA/FABRIC INSTALLATION.

CONTROL DUST BY WATERING OR OTHER APPROVED METHODS AS NECESSARY, OR AS DIRECTED BY THE

THE CONTRACTOR IS RESPONSIBLE FOR THE INSPECTION AND MAINTENANCE DURING CONSTRUCTION OF ALL STORMWATER FACILITIES INSTALLED OR AFFECTED BY THE PROJECT. REMOVE SEDIMENT OR DEBRIS COLLECTED WITHIN THESE FACILITIES FROM THE PROJECT WORK PRIOR TO THE OWNER'S ACCEPTANCE.

A HIGH WATER TABLE IS NOT ANTICIPATED. HOWEVER, IF THE WATER TABLE IS ENCOUNTERED DURING EXCAVATION. TEMPORARILY LOWER THE WATER TABLE BY PUMPING AS INDICATED IN THE DEWATERING SUMP DETAIL. INSTALL A DEWATERING BASIN AS INDICATED IN THE DEWATERING BAG DETAIL AND PROVIDE A DEWATERING PLAN DEPICTING PROPOSED DEWATERING LOCATION. DIRECT THE PUMP DISCHARGE TO THIS BASIN TO PREVENT SEDIMENTS FROM LEAVING THE CONSTRUCTION AREA. INSTALL ADDITIONAL BASINS IF REQUIRED. INSTALL THE BASIN AS INDICATED ON DRAWINGS IF SO NOTED. OTHERWISE INSTALL THE BASIN(S) WITHIN THE LIMIT OF DISTURBANCE INDICATED BY THE SILT FENCE OR

PRIOR TO ANY DEWATERING, THE DEWATERING PLAN MUST BE APPROVED BY THE ENGINEER.

IF DEWATERING IS NECESSARY DURING CONSTRUCTION. IMPLEMENT THE PROPER ESC MEASURES ON SITE TO PREVENT EROSION OR SEDIMENT RUNOFF. THESE MEASURES CAN INCLUDE DEWATERING BAGS, TEMPORARY STRAWBALES, SILT FENCES, SILT SOCKS AND/OR OTHER APPROVED DEVICES AS INDICATED IN THE DETAILS.


STORMWATER FACILITY OPERATION & MAINTENANCE:

THE CONTRACTOR IS RESPONSIBLE FOR THE STORMWATER POLLUTION PREVENTION PLAN (SWPPP) AND THE PROPER INSPECTION AND MAINTENANCE OF ALL STORMWATER MANAGEMENT FACILITIES AS OUTLINED BELOW UNTIL SUCH TIME THAT THE ROADWAYS AND ASSOCIATED UTILITIES ARE ACCEPTED BY THE OWNER AND THE ENGINEER. REFER TO THE APPROVED 4 SWPPP FOR ADDITIONAL MAINTENANCE REQUIREMENTS.


- MAINTAIN A WORKING COPY OF THE SWPPP ON SITE AT ALL TIMES
- INSPECT AND RESTORE/CLEAN ALL FACILITIES (INLETS, MANHOLES, INFILTRATION BASINS, ETC.) OF SEDIMENT AND DEBRIS PRIOR TO THE OWNER'S ACCEPTANCE.
- REMOVE AND DISPOSE ALL SEDIMENT AND DEBRIS AT A PRE-APPROVED LOCATION AS APPROVED BY THE TOWN.
- INSPECT AFTER EVERY MAJOR RAINFALL EVENT FOR THE ENTIRE DURATION OF THE CONSTRUCTION PROJECT AND THE FIRST 3 MONTHS AFTER CONSTRUCTION TO ENSURE PROPER STABILIZATION AND CONSTRUCTION.
- SPECIFIC MAINTENANCE REQUIRED DURING CONSTRUCTION AS FOLLOWS:
- DRAINAGE STRUCTURES (INLETS, MANHOLES & CATCHBASINS): ALL DRAINAGE STRUCTURES WILL BE INSPECTED TO MONITOR FOR PROPER OPERATION, COLLECTION OF LITTER OR TRASH, AND STRUCTURAL DETERIORATION. THE BASINS WILL BE CLEANED OF SEDIMENT (INCLUDING SUMPS) AS NECESSARY, AND REPAIRED WHEN REQUIRED.
- B. SEDIMENT FOREBAY: REMOVE SEDIMENT BUILD-UP ON THE FLOOR OF THE FOREBAY AND PROPERLY DISPOSE OF IN A PRE-APPROVED LOCATION ONCE EVERY YEAR, OR MORE OFTEN AS NECESSARY TO LIMIT SEDIMENT BUILDUP TO LESS THAN 50 PERCENT OF THE DESIGN VOLUME.
- BIORETENTION SYSTEMS AND BIOSWALES: INSPECT AFTER STORM EVENTS GREATER THAN OR EQUAL TO THE 1-YEAR! 24-HOUR PRECIPITATION EVENT, OR MORE FREQUENTLY AS NEEDED. REMOVE ANY TRASH AND/OR DEBRIS. CORRECT ANY EROSION OR GULLYING. REMOVE AND REPLACE ILL-ESTABLISHED, DEAD OR SEVERELY DISEASED
- . <u>ENHANCED TREE TRENCH:</u> INSTALL CATCH BASIN INSERTS. INSPECT STRUCTURE AFTER STORM EVENTS GREATER THAN OR EQUAL TO THE 1-YEAR, 24-HOUR PRECIPITATION EVENT, OR MORE FREQUENTLY AS NEEDED. THE BASINS
- TREE FILTER PITS: ALL TREE FILTER PITS WILL BE INSPECTED TO MONITOR FOR PROPER OPERATION, COLLECTION OF LITTER OR TRASH, AND STRUCTURAL DETERIORATION. THE BASINS AND SEDIMENT FOREBAYS WILL BE CLEANED OF SEDIMENT (INCLUDING SUMPS) AS NECESSARY, AND REPAIRED WHEN REQUIRED.


WILL BE CLEANED OF SEDIMENT (INCLUDING SUMPS) AS NECESSARY, AND REPAIRED WHEN REQUIRED.


ROUTINE MAINTENANCE: OTHER ROUTINE MAINTENANCE INCLUDES THE REMOVAL OF TRASH AND LITTER FROM PAVED AND PERIMETER AREAS, AND ANNUAL STREET AND PARKING LOT SWEEPING AFTER THE SPRING THAW TO AVOID EXCESSIVE ACCUMULATION OF SEDIMENT IN THE DRAINAGE SYSTEM. INSPECT THE PIPES DRAINING THE PROJECT ANNUALLY FOR PROPER FLOW.



PIPE PROTECTION OR APPROVED EQUIVALENT SILT SACK **NOT TO SCALE**







1. FENCING SHALL BE ORANGE RESINET SM60 BARRIER FENCE "SNOW FENCE" OR APPROVED

2. POST SHALL BE HOT ROLLED RAIL STEEL AND FORMED INTO A "T". DIMENSIONS OF "T" POST SECTION APPROXIMATELY 1 7/16" X 1 5/16" X 1/8" X 6' (SIX FEET) LONG. THE POST SHALL BE PAINTED GREEN OR **GALVANIZED**

3. THE FENCING SHALL REMAIN IN PLACE UNTIL ALL EXCAVATION HAS BEEN COMPLETED AND THE SURFACE HAS BEEN RE-ESTABLISHED

2" X 2" X 4' WOODEN STAKE 1. FENCE FABRIC TO BE 36-INCHES WIDE MINIMUM AND TO BE SECURELY FASTENED TO BEANPOLES. 6" MIN OF FABRIC TO BE BELOW SUPPORT NET 24" DIA. GROUND SURFACE (BACKFILLED OR TOE-ED ACCESS SILT FENCE **EXPOSED** 48" DIA. (MIN.) **ALTERNATE TOP SLAB** BELOW GROUND ACCESS FINISH GRADE SEDIMENT LADEN RUNOF SECTION B

UNDISTURBED

PUMP DISCHARGE HOSE

─ FLOW FROM PUMP →

SPOUT SEWN INTO BAG -

TIE DOWN STRAP

(SEE NOTES

FLOW FROM PUMP -

DEWATERING BAG DETAIL

EROSION/SILTATION —

WORK AREA

CONTROL FENCE AS

NOTED -SEE PLANS &

MULCH SOCK -

(12" - 18" TYPICAL)

SEDIMENT MULCH SOCK

. MULCH SOCK MANUFACTURER TO BE SILT SOXX OR ENGINEER APPROVED EQUAL.

SEDIMENT MULCH SOCK TO BE FILLED WITH MULCH COMPOST AND/OR WOODY MULCH PER

4. FOLLOWING CONSTRUCTION AND SITE STABILIZATION, COMPOST MATERIAL TO BE REMOVED

SILT SOCK

TIE DOWN STRAP (SEE NOTES)

SPOUT SEWN INTO BAG

DEWATERING BAG

ON AGGREGATE

OR STRAW

UNDERLAY

+++++

STRAW BALE UNDERLAY

SECTION A - A

WOODEN

AREA TO BE

PROTECTED

FILTERED WATER

- DEWATERING

INSTALLATION NOTES:

IS NEEDED)

MAINTENANCE:

. PLACE LIFTING STRAPS (NOT

INCLUDED) UNDER THE UNIT TO

STABILIZED AREA OVER DENSE

INSERT DISCHARGE HOSE FROM

A MINIMUM OF SIX INCHES AND

FACILITATE REMOVAL AFTER USAGE

VEGETATION, STRAW, OR GRAVEL (IF

AN INCREASED DRAINAGE SURFACE

PUMP INTO DANDY DEWATERING BAG

TIGHTLY SECURE WITH ATTACHED TIE

DOWN STRAP TO PREVENT WATER

PLACE ABSORBENT BOOM INTO THE

SEDIMENT OR WHEN SEDIMENT HAS

REDUCED THE FLOW RATE OF THE

6. IF USING OPTIONAL OIL ABSORBENTS

REMOVE AND REPLACE ABSORBENT

PILLOW WHEN NEAR SATURATION

5. REPLACE THE UNIT WHEN 1/2 FULL OF PUMP DISCHARGE HOSE

STAKE ON 10'

AREA TO BE

LINEAL SPACING

ALL MATERIAL TO MEET MANUFACTURER'S SPECIFICATIONS.

OR DISPERSED ON SITE, AS APPROVED BY THE ENGINEER.

MANUFACTURER'S REQUIREMENTS.

FROM FLOWING OUT OF THE UNIT

WITHOUT BEING FILTERED

DANDY DEWATERING BAG

PUMP DISCHARGE TO AN

IMPRACTICAL RATE

WATER \


INTO GROUND).

BEAN POLES

FLOW


4. IF USING OPTIONAL ABSORBENTS.

UNFOLD DANDY DEWATERING BAG ON




JOINING SECTIONS OF FENCE

SILT FENCE




1. ALL SECTIONS TO BE DESIGNED FOR H-20 2. COPOLYMER MANHOLE STEPS TO BE INSTALLED AT 12" O.C. FOR THE FULL DEPTH OF THE 3 PROVIDE "V" KNOCKOUTS FOR PIPES WITH 2" MAX CLEARANCE TO OUTSIDE OF PIPE. MORTAR ALL PIPE CONNECTIONS. 4. JOINT SEALANT BETWEEN PRECAST SECTIONS TO BE PREFORMED BUTYL RUBBER. 5 DRAIN MANHOLE FRAME AND COVER TO BE SET IN FULL 12" MORTAR BED. ADJUST TO GRADE WITH PRECAST CONCRETE RISER OR BRICK.

6. DO NOT PLACE MORTAR BED AROUND STRUCTURE UNTIL IT IS AT THE REQUIRED FINISH ELEVATION AND ALIGNMENT. 7. FRAME AND COVER TO CONFORM TO MASSACHUSETTS STANDARDS HEAVY DUTY (EAST JORDAN, NEENAH, OR APPROVED EQUIVALENT).




PRECAST DRAIN MANHOLE (DMH)



TYPICAL DRAINAGE STRUCTURE FRAME AND COVER/GRATE

1. ALL SECTIONS TO BE DESIGNED FOR H-20 2 PROVIDE "V" KNOCKOUTS FOR PIPES WITH 2" MAX. CLEARANCE TO OUTSIDE OF PIPE. MORTAR ALL PIPE CONNECTIONS. 3. JOINT SEALANT BETWEEN PRECAST SECTIONS TO BE PREFORMED BUTYL 24" SQUARE OPENING 4. CATCH BASIN FRAME AND GRATE TO BE RISER OR BRICK ALTERNATE ECCENTRIC CONE SECTION 5. DO NOT PLACE MORTAR BED AROUND 24" SQUARE OPENING FINISH ELEVATION AND ALIGNMENT. FRAME AND COVER TO CONFORM TO 8" (MIN.) EQUIVALENT) —— 48" DIA. (MIN.) ———



PRECAST CONCRETE CATCH BASIN (CB) WITH HOOD


APPROVED COMPACTED SUBGRADE


--| |-- 1" LIFT HOLE


SET IN FULL 12" WIDE MORTAR BED. ADJUST TO GRADE WITH PRECAST CONCRETE STRUCTURE UNTIL IT IS AT THE REQUIRED

MASSACHUSETTS STANDARDS HEAVY DUTY (EAST JORDAN, NEENAH, OR APPROVED . HDPE PIPE HOOD TO BE 90° BEND

3/4" CRUSHED STONE







BIORETENTION CONSTRUCTION SEQUENC

- THE FOLLOWING CONSTRUCTION SEQUENCE IS TO BE USED AS A GENERAL GUIDELINE. COORDINATE WITH THE OWNER, ENGINEERS, AND LANDSCAPE ARCHITECTS AND SUBMIT A PROPOSED CONSTRUCTION SEQUENCE FOR REVIEW AND APPROVAL PRIOR TO CONSTRUCTION.
- 1. CONDUCT A PRE-CONSTRUCTION MEETING.
- 2. CHECK FOR EXISTING UTILITIES PRIOR TO ANY EXCAVATION.
- 3. CLEAR AND GRUB THE PROPOSED BIORETENTION AREA
- 4. ROUGH GRADE THE BIORETENTION AREA DURING GENERAL CONSTRUCTION.
- 5. EXCAVATE PRETREATMENT CELLS AND/OR SEDIMENT FOREBAYS PRIOR TO BIORETENTION
- 6. DO NOT CONSTRUCT THE BIORETENTION AREA UNTIL ALL DISTURBED AREAS WITHIN THE CONTRIBUTING DRAINAGE AREAS HAVE BEEN GRADED AND STABILIZED.
- 7. INSTALL TEMPORARY EROSION AND SEDIMENT CONTROLS TO DIVERT STORMWATER AWAY FROM THE
- 8. EXCAVATE THE BIORETENTION FACILITY TO THE BOTTOM INVERT OF THE SUBDRAIN SYSTEM. IF USED FOR TEMPORY STORMWATER MANAGEMENT DURING CONSTRUCTION PROVIDE A SURFACE ELEVATION AT A MINIMUM 1-FOOT ABOVE THE BOTTOM OF UNDERDRAIN ELEVATION AS SHOWN IN THE BIORETENTION SCHEDULE. THIS ALLOWS FOR AN OVER-DIG OF THE ACCUMULATED SEDIMENT FROM
- WITHIN THE BIORETENTION AREA PRIOR TO MEDIA/FABRIC INSTALLATION 9. PRIOR TO THE INSTALLATION OF FILTER FABRIC AND MEDIA WITHIN THE BIORETENTION AREAS, REMOVE AND PROPERLY DISPOSE OF SEDIMENT ACCUMULATED IN ANY PARTIALLY CONSTRUCTED OR
- TEMPORARY BIORETENTION/DRAINAGE AREA USED FOR SEDIMENT CONTROL DURING CONSTRUCTION. 10. MANDATORY NOTIFICATION/APPROVAL OF THE PROJECT ENGINEER IS REQUIRED PRIOR TO
- PROCEEDING WITH NEXT STAGE. <u>CALL THE ENGINEER (HORSLEY WITTEN GROUP, INC.) AT 508-833-6600 PRIOR TO 12:00 NOON THE PROCEEDING DAY TO ARRANGE FOR ANY REQUESTED FIELD VISITS.</u> 11. INSTALL THE FILTER FABRIC ALONG THE EXCAVATION SIDE WALLS. <u>ENGINEER FIELD VISIT AND REPORT</u>
- 12. RIP THE BOTTOM SOILS TO A DEPTH OF SIX INCHES TO PROMOTE GREATER INFILTRATION.
- 13. INSTALL THE OVERFLOW OUTLET STRUCTURE AS SPECIFIED IN THE DRAWINGS.
- 14. INSTALL UNDERDRAIN AS INDICATED ON DRAWINGS. <u>ENGINEER FIELD VISIT AND REPORT REQUIRED</u> PRIOR TO COVERING THE UNDERDRAIN. SEE NOTE 10
- 15. INSTALL PEA GRAVEL LAYER AS INDICATED ON DRAWINGS. 16. DELIVER APPROVED BIORETENTION SOIL AND STORE ON ADJACENT IMPERVIOUS AREA OR PLASTIC
- 17. BACKFILL WITH APPROVED BIORETENTION SOIL TO THE DESIGN GRADE (UN-COMPACTED) AS INDICATED ON DRAWINGS. THE CONTRACTOR MUST SUBMIT A SOIL SAMPLE (2 LBS) TO THE ENGINEER PRIOR TO
- 18. STABILIZE ALL REMAINING DISTURBED AREAS AND SIDE SLOPES WITH SEEDING, HYDROSEEDING, AND/OR EROSION CONTROL BLANKETS AS INDICATED ON DRAWINGS. ENGINEER FIELD VISIT AND REPORT REQUIRED SEE NOTE 10.
- 19. INSTALL BIORETENTION PLANTINGS AS INDICATED ON DRAWINGS. DO NOT PLANT BEFORE THE REMAINING DISTURBED AREAS SURROUNDING THE FACILITY ARE STABILIZED.
- 20. INSTALL MULCH LAYER AS INDICATED ON DRAWINGS. <u>THE CONTRACTOR MUST SUBMIT A MULCH SAMPLE (1 GALLON) TO THE ENGINEER PRIOR TO DELIVERY TO THE SITE.</u>
- 21. CONDUCT FINAL CONSTRUCTION INSPECTION WITH ENGINEER. <u>ENGINEER FIELD VISIT AND REPORT</u> REQUIRED SEE NOTE 10 BELOW.
- 22. REMOVE REMAINING EROSION AND SEDIMENT CONTROLS ONLY AFTER SURROUNDING DISTURBED AREAS HAVE BEEN PROPERLY STABILIZED.

CONSTRUCTION NOTES

SOIL DELIVERY TO THE SIT

- A. VERIFY LAYOUT AND ORIENTATION OF BIORETENTION AREA AND CONNECTIONS.
- B. VERIFY EXCAVATION BASE IS READY TO RECEIVE WORK AND EXCAVATIONS, DIMENSIONS, AND ELEVATIONS ARE AS INDICATED ON DRAWINGS.
- A. CALL DIGSAFE AT 1-888-DIG-SAFE (1-888-344-7233) NOT LESS THAN THREE BUSINESS DAYS BEFORE
- B. REQUEST UNDERGROUND UTILITIES TO BE LOCATED AND MARKED WITHIN AND SURROUNDING
- CONSTRUCTION AREAS.
- C. IDENTIFY REQUIRED LINES, LEVELS, CONTOURS, AND DATUM. D. CLEAR AND GRUB THE PROPOSED BIORETENTION AREA.

EXCAVATED FROM THE SIDE.

- A. EXCAVATE BIORETENTION AREA IN ACCORDANCE WITH GENERAL NOTES AND SPECIFICATIONS.
- TO MINIMIZE COMPACTION. WORK EXCAVATORS OR BACKHOES FROM THE SIDES TO EXCAVATE THE BIORETENTION AREA TO ITS APPROPRIATE DESIGN DEPTH AND DIMENSIONS. USE EXCAVATING EQUIPMENT WITH ADEQUATE REACH SO THEY DO NOT WORK IN THE FOOTPRINT OF THE BIORETENTION AREA. IF APPLICABLE AND PER THE ENGINEERS DIRECTION USE A CELL CONSTRUCTION APPROACH IN LARGER BIORETENTION BASINS, WHEREBY THE BASIN IS SPLIT INTO 500 TO 1000 SQUARE FOOT TEMPORARY CELLS WITH A 10 TO 15 FOOT EARTH BRIDGE IN BETWEEN, SO THAT CELLS CAN BE
- C. EXCAVATE AND SEAL ANY PRETREATMENT CELLS AND/OR SEDIMENT FOREBAYS FIRST AND SEALED TO TRAP SEDIMENTS PER THE DRAWINGS.
- D. ROUGH GRADE THE BIORETENTION AREA DURING GENERAL CONSTRUCTION. EXCAVATE THE BIORETENTION FACILITIES TO WITHIN 1 FOOT OF UNDERDRAIN BOTTOM.

E. IF THE BIORETENTION AREA IS TO BE USED AS A TEMPORARY DRAINAGE STORAGE BASIN DURING THE

EARLY STAGES OF PROJECT CONSTRUCTION, THE SIDE SLOPES SHOULD BE TEMPORARILY STABILIZED AND SILT FENCE INSTALLED ALONG THE TOE OF THE ROUGH GRADED BIORETENTION SLOPES TO MINIMIZE EXCESSIVE SEDIMENTATION OF THE BIORETENTION FLOOR.

- A. MINIMIZE COMPACTION OF BOTH THE BASE OF THE BIORETENTION AREA AND THE REQUIRED BACKFILL. COMPACTION WILL SIGNIFICANTLY CONTRIBUTE TO DESIGN FAILURE.
- B. USE EXCAVATOR OR BACKHOES TO EXCAVATE THE BIORETENTION AREA

E. DO NOT COMPACT BIORETENTION SOIL WITH MECHANICAL EQUIPMENT.

C. FORM BOTTOM OF EXCAVATION TO CORRECT ELEVATION.

- C. IF THE BIORETENTION AREA IS EXCAVATED USING A LOADER, USE ONLY WIDE TRACK OR MARSH TRACK EQUIPMENT, OR LIGHT EQUIPMENT WITH TURF TYPE TIRES. USE OF EQUIPMENT WITH NARROW TRACKS OR NARROW TIRES. RUBBER TIRES WITH LARGE LUGS. OR HIGH PRESSURE TIRES CAUSE EXCESSIVE COMPACTION RESULTING IN REDUCED INFILTRATION RATES AND STORAGE VOLUMES AND
- D. COMPACTION CAN BE ALLEVIATED AT THE BASE OF THE BIORETENTION FACILITY BY USING A PRIMARY TILLING OPERATION SUCH AS A CHISEL PLOW, RIPPER, OR SUBSOILER. THESE TILLING OPERATIONS ARE PERFORMED TO REFRACTURE THE SOIL PROFILE THROUGH THE 12-IN COMPACTION ZONE.
- SUBSTITUTE METHODS MUST BE APPROVED BY THE ENGINEER. ROTOILLERS TYPICALLY DO NOT TILL DEEP ENOUGH TO REDUCE THE EFFECTS OF COMPACTION FROM HEAVY EQUIPMENT.

5. EMBANKMENT/BERM FILL

- A. CONSTRUCT EMBANKMENT/BERM IN ACCORDANCE WITH SPECIFICATIONS AND AS INDICATED ON DRAWINGS
- 6. INSTALLATION
- A. DO NOT CONSTRUCT THE BIORETENTION AREA UNTIL ALL DISTURBED AREAS WITHIN THE
- CONTRIBUTING DRAINAGE AREAS HAVE BEEN GRADED AND STABILIZED. B. REMOVE SEDIMENT ACCUMULATED ALONG THE EXCAVATION FLOOR DURING SITE CONSTRUCTION PRIOR TO CONTINUING WITH THE BIORETENTION FACILITY CONSTRUCTION.
- D. IF INFILTRATION IS PROMOTED, THEN RIP THE BOTTOM SOILS TO A DEPTH OF SIX INCHES TO PROMOTE GREATER INFILTRATION.
- E. INSTALL THE FILTER FABRIC ALONG THE EXCAVATION SIDE WALLS AS SPECIFIED IN THE DRAWINGS. IF FILTER FABRIC IS TO BE INSTALLED PLACE THE FILTER FABRIC ON THE SIDES OF THE BIORETENTION AREA WITH A MINIMUM SIX INCH OVERLAP AT ALL JOINTS.
- F. INSTALL ANY TEMPORARY EROSION AND SEDIMENT CONTROLS TO DIVERT STORMWATER AWAY FROM THE BIORETENTION AREA DURING FINAL CONSTRUCTION AND UNTIL IT IS COMPLETED. SPECIAL PROTECTION MEASURES SUCH AS EROSION CONTROL FABRICS MAY BE NEEDED TO PROTECT VULNERABLE SIDE SLOPES FROM EROSION DURING THE CONSTRUCTION PROCESS.
- G. ESTABLISH ELEVATIONS AND PIPE INVERTS FOR INLETS AND OUTLETS AS INDICATED ON DRAWINGS
- H. INSTALL THE OVERFLOW OUTLET STRUCTURE AS INDICATED ON DRAWINGS.
- I. INSTALL UNDERDRAIN, INCLUDING 4 INCH PERFORATED PIPE, GRAVEL AND FILTER FABRIC ON TOP OF THE UNDERDRAIN GRAVEL AS INDICATED ON DRAWINGS. PLACE GRAVEL AROUND THE UNDERDRAIN PIPE AS INDICATED IN THE DETAILS. OBSERVATION WELLS AND/OR CLEAN-OUT PIPES MUST BE PROVIDED (SEE PLANS FOR LOCATION).
- J. INSTALL PEA GRAVEL LAYER AS INDICTED ON DRAWINGS.
- K. DELIVER APPROVED BIORETENTION SOIL AND STORE ON ADJACENT IMPERVIOUS AREA OR PLASTIC SHEETING.

7. BACKFILLING

A. BACKFILL WITH APPROVED BIORETENTION SOIL TO THE DESIGN GRADE AS SPECIFIED IN THE

B. PLACE SOIL IN 12 INCH LIFTS UNTIL DESIRED TOP ELEVATION OF BIORETENTION SOIL IS ACHIEVED. DO

NOT USE HEAVY EQUIPMENT WITHIN THE BIORETENTION BASIN. HEAVY EQUIPMENT CAN BE USED AROUND THE PERIMETER OF THE BASIN TO SUPPLY SOILS AND SAND. WAIT 3 DAYS TO CHECK FOR SETTLEMENT, AND ADD ADDITIONAL MEDIA AS NEEDED

C. DO NOT COMPACT BIORETENTION SOIL WITH MECHANICAL EQUIPMENT.

AND/OR EROSION CONTROL BLANKETS AS INDICATED ON DRAWINGS.

D. GRADE BIORETENTION MATERIALS WITH LIGHT EQUIPMENT SUCH AS A COMPACT LOADER OR A

DOZER/LOADER WITH MARSH TRACKS. E. STABILIZE ALL REMAINING DISTURBED AREAS AND SIDE SLOPES WITH SEEDING, HYDROSEEDING,

- 8. PLANTING A. PLANT BIORETENTION AREA IN ACCORDANCE WITH PLANTING PLANS AND SPECIFICATIONS.
- B. THE PRIMARY FUNCTION OF THE BIORETENTION STRUCTURE IS TO IMPROVE WATER QUALITY. DO NOT ADD FERTILIZERS OR OTHER SOIL AMENDMENTS TO THE BIORETENTION SOILS UNLESS INSTRUCTED BY THE ENGINEER. THE PLANTING SOIL SPECIFICATIONS PROVIDE ENOUGH ORGANIC MATERIAL TO ADEQUATELY SUPPLY NUTRIENTS FROM NATURAL CYCLING.
- C. INSTALL BIORETENTION PLANTINGS AS INDICATED ON DRAWINGS. WATER DURING WEEKS OF NO RAIN FOR THE FIRST TWO MONTHS.
- D. DO NOT PLANT BEFORE THE REMAINING DISTURBED AREAS SURROUNDING THE FACILITY ARE
- STABILIZED. E. REMOVE SEDIMENT ACCUMULATED IN THE BIORETENTION AREA DURING THE PLANTING PHASE.
- F. IF SUITABLE VEGETATIVE COVER HAS NOT BEEN ESTABLISHED ALONG THE BIORETENTION SIDE SLOPES PRIOR TO PLANTING, INSTALL A SILT FENCE PERIMETER AT THE TOE OF THE BIORETENTION SLOPES AND LEAVE IN PLACE UNTIL AN APPROVED VEGETATIVE COVER HAS BEEN ESTABLISHED.
- G. INSTALL MULCH LAYER AS INDICATED ON DRAWINGS. MIX APPROXIMATELY HALF OF THE SPECIFIED MULCH LAYER INTO THE BIORETENTION SOIL TO A DEPTH OF APPROXIMATELY 4 INCHES TO HELP FOSTER A HIGHLY ORGANIC SURFACE LAYER.
- H. REMOVE REMAINING EROSION AND SEDIMENT CONTROLS ONLY AFTER SURROUNDING DISTURBED AREAS HAVE BEEN PROPERLY STABILIZED.
- I. CONDUCT FINAL CONSTRUCTION INSPECTION WITH ENGINEER.

9. CLEAN UP

A. AFTER COMPLETION OF THE WORK, REMOVE AND PROPERLY DISPOSE ALL DEBRIS, CONSTRUCTION MATERIALS, RUBBISH, EXCESS SOIL, ETC., FROM THE PROJECT SITE. REPAIR PROMPTLY ANY IDENTIFIED DEFICIENCIES AND LEAVE THE PROJECT SITE IN A CLEAN AND SATISFACTORY CONDITION.

MATERIAL SPECIFICATIONS

- SUBMIT SOIL SAMPLE (2LBS) AND TESTING ANALYSIS RESULTS BY A QUALIFIED SOIL TESTING LABORATORY INDICATING AND INTERPRETING TEST RESULTS FOR COMPLIANCE WITH THE FOLLOWING PARAMETERS: A. UNIFORM SOIL MIX, FREE OF NOXIOUS WEEDS AND STONES, STUMPS, ROOTS OR OTHER SIMILAR
- OBJECTS LARGER THAN 1 INCH.
- B. PROVIDE USDA UNIFIED SOIL CLASSIFICATION: LOAMY SAND C. PROVIDE A TEXTURAL ANALYSIS INCLUDING THE GRADATION AND PERCENTAGES OF SAND, SILT, AND
- 85-88% SAND (< 10% COARSE SAND) 8-12% SILT AND CLAY (< 2% CLAY)
- D. ORGANIC MATTER: 3%
- WELL AGED (6-12 MONTHS), WELL AERATED, LEAF COMPOST OR APPROVED EQUIVALENT
- E. PROVIDE A SOIL TEST OF THE BIORETENTION SOIL FOR CONFORMANCE TO THE FOLLOWING CRITERIA: PH RANGE:
 - MAGNESIUM: MINIMUM 32 PPM
 - PHOSPHOROUS (P2O5): NOT TO EXCEED 69 PPM.
 - POTASSIUM (K2O): MINIMUM 78 PPM.
- SOLUBLE SALTS: NOT TO EXCEED 500 PPM. IF THE SOIL PH IS NOT WITHIN THE ACCEPTABLE RANGE, AMEND WITH LIME TO RAISE THE PH OR WITH IRON SULFATE TO LOWER THE PH, AS NECESSARY. ALL TESTING SHOULD BE PERFORMED BY THE SAME TESTING FACILITY TO MAINTAIN CONSISTENT RESULTS. SUBMIT THE SOIL SAMPLE RESULTS TO
- F. VOLUME OF FILTER MEDIA BASED ON 110% OF PLAN VOLUME TO ACCOUNT FOR SETTLING OR COMPACTION.

THE ENGINEER REVIEW AND APPROVAL PRIOR TO DELIVERY TO THE PROJECT SITE.

G. DO NOT MIX, DUMP OR STORE ANY OTHER MATERIALS OR SUBSTANCES THAT MAY BE HARMFUL TO PLANT GROWTH OR PROVE A HINDRANCE TO THE PLANTING MAINTENANCE OR OPERATIONS WITHIN THE BIORETENTION AREA.


2. MULCH

- A. FINE SHREDDED WELL AGED (6 MONTH MINIMUM) HARDWOOD MULCH. HARDWOOD MULCH IS PREFERRED TO PREVENT FLOATING. IF HARDWOOD MULCH IS NOT AVAILABLE A FINELY DOUBLE SHREDDED, WELL AGED, ORGANIC DARK PINE MULCH MAY BE ACCEPTABLE ON A CASE BY CASE BASIS PER SAMPLE SUBMITTAL AND ENGINEER REVIEW.
- B. A MULCH SAMPLE MUST BE SUBMITTED AND APPROVED BY THE ENGINEER PRIOR TO DELIVERY TO THE PROJECT SITE.


3. FILTER FABRIC

- A. NON-WOVEN GEOTEXTILE FABRIC WITH FLOW RATE OF > 110 GALLON/MINUTES/SQUARE FOOT.
- B. CLASS "C" APPARENT OPENING SIZE (ASTM-D-4751). C. GRAB TENSILE STRENGTH (ATSM-D-4632) BURST STRENGTH (ASTM-D-4833).
- 4. PEA GRAVEL
- A. 3/8" WASHED STONE
- 5. UNDERDRAIN GRAVEL
- A. 3/4" CRUSHED WASHED STONE, CLEAN AND FREE OF ALL FINES AND MEETING AASHTO M-43. 6. <u>PIPE</u>
- A. UNDERDRAIN 4" RIGID SCHEDULE 40 PVC PIPE, WITH 3/8" PERFORATIONS @ 6" O.C. MEETING ASTMD 1785 OR AASHTO M-278. T'S AND Y'S FITTINGS AS REQUIRED FOR THE UNDERDRAIN CONFIGURATION INDICATED ON
- B. CONNECTIONS TO STORM DRAIN SYSTEM.
- C. UNDERDRAIN CLEANOUTS
- NON PERFORATED SCHEDULE 40 PVC PIPE, PVC ELBOW, CAP, AND ALL ASSOCIATED FITTINGS.
- 7. EROSION CONTROL BLANKET (3:1 SIDE SLOPES ONLY)
- A. WOVEN, 100% BIODEGRADABLE JUTE FIBER 7.70 LBS/1000 SQFT.
- BIONET S150BN OR APPROVED EQUIVALENT. 8. PLANTS
- A. AS INDICATED ON DRAWINGS.
- 9. SEED (SIDE SLOPES ONLY) A. NEW ENGLAND CONSERVATION/WILDLIFE/MIX OR APPROVED EQUIVALENT.
- B. APPLICATION RATE 25 LBS/ ACRES OR PER SEED MANUFACTURER'S REQUIREMENTS.
- 10. OUTLET STRUCTURE
- A. SIZE AS INDICATED ON DRAWINGS.
- B. FIBERGLASS REINFORCED PLASTIC MANHOLES OF SIZE INDICATED ON DRAWINGS.

	Х	ELEV. A	Y	ELEV. B	ELEV. C
No.	Ponding Depth (ft)	Bottom of Bio Area (ft) ¹	Bio Soil Depth (in)	Bottom Bio Soil (ft)	Bottom of Bed (ft)
1	0.33	30.80	18.00	29.30	28.80
2	0.50	30.85	15.00	20.60	20.10



BIORETENTION AREA




BIO OVERFLOW OUTLET


BY "NYLOPLAST" OR APPROVED EQUIVALENT

OF 3" WASHED CRUSHED STONE (MA HIGHWAY

M2.01.0 OR EQUIV.). CONNECT TO INLET



BIORETENTION CLEANOUT NOT TO SCALE



BIORETENTION AREA

NOT TO SCALE

OR BACKFILL MATERIAL

PROVIDE A CLEAN EDGE -AT INFLOW INTERFACE CURB INLET SEE DETAIL **GUTTER LINE** HEAVY DUTY LANDSCAPE EDGING BEDDING MATERIAL PER MANUFACTURER **BOTTOM OF BED** REQUIREMENTS NO FILTER FABRIC ALONG BOTTOM OF THE **BIORETENTION BED**

- WEIR NOTCH - SEE DETAIL HEAVY DUTY STEEL LANDSCAPE -PLANTABLE CONCRETE PAVER (SEE DETAIL) SEE SITE PLAN 4:1 MAX SLOPE SEE LANDSCAPE PLANS FOR SLOPE TREATMENT

BARNSTABLE

MARSTONS MILLS VILLAGE CENTER IMPROVEMENTS

NO. SHEET

13 | 108

CONSTRUCTION DETAILS-DRAINAGE & UTILITIES (2)

SHEET 9 OF 10

AGGREGATE INFILI

CRUSHED STONE

REFER TO MANUFACTURERS REQUIREMENTS FOR ADDITIONAL INSTALLATION REQUIREMENTS

PLANTABLE CONCRETE PAVER

SEDIMENT FOREBAY

— LENGTH AND WIDTH VARIES - SEE PLANS →

--- PLANTABLE/PERMEABLE

SECTION B - B

CLEAN EDGE -

AT CHECKDAM

CONCRETE PAVER

FILTER FABRIC AROUND PERIMETER AND BOTTOM OF STONE BASE. KEY IN MINIMUM 6".

PAVER MAT

PLAN VIEW

3/8" MINUS CRUSHED ANGULAR ROCK OR LESS

BROOM FINISH JUST BELOW DRIVABLE GRASS

½" NOMINAL COMPACTED CLEAN -

SHARP SAND (ASTM C33) FOR

FILTER FABRIC OVERLAP

EQUIVALENT

SUBBASE SLOPED TO MATCH PAVER -

PLANTABLE CONCRETE PAVER NOTES:

(NON-WOVEN MIRAFI

140N OR APPROVED

FILTER FABRIC -

MAT SURFACE. SEE SPECIFICATIONS

AGGREGATE INFILL MATERIAL:

SLOPE

3" PEA GRAVEL

PLANTING SOIL

AGGREGATE INFILL.

INFILL DETAIL

SPECIFICATIONS

OF THE MATS WITH

MAT EDGES.

- PLANTABLE CONCRETE PAVERS SYSTEM

CRUSHED STONE RESERVOIR MEETING

BIORETENTION/BIOSWAL

(SEE DETAIL)

- GRANITE CHECK DAI

SEE DETAIL

AASHTO #57 COMPACTED SUBGRADE, 95% MODIFIED PROCTOR DENSITY

OR APPROVED EQUIVALENT- SEE

SAND (ASTM C33) TO

FILL JOINTS BETWEEN

SECTION A - A

SEE SPECIFICATIONS FOR PLANTABLE/PERMEABLE PAVER REQUIREMENTS. INSTALL PLANTABLE/PERMEABLE PAVER SYSTEM PER MANUFACTURERS REQUIREMENTS.

SHAPE FOREBAY AS REQUIRED WITH MIN. 6" SIDE SLOPE DEPTH. LANDSCAPE EDGING: HEAVY DUTY STEEL LANDSCAPE EDGING (2" THICKNESS) WITH NATURAL FINISH SEE PLANS FOR DIMENSIONS GRADING AND ELEVATIONS FOR SEDIMENT FOREBAY

> SEDIMENT FOREBAY NOT TO SCALE

SUBGRADE

- SUBMIT TO THE LANDSCAPE ARCHITECT FOR REVIEW AND APPROVAL ALL REQUIRED LANDSCAPE SUBMITTALS AS DESCRIBED IN THE SPECIFICATIONS INCLUDING A PLANT LIST WITH PLANT SIZE AND QUANTITIES TO BE ORDERED PRIOR TO DELIVERY TO THE PROJECT SITE.
- FURNISH AND INSTALL ALL PLANTS AS SHOWN ON THE DRAWINGS AND IN THE SIZE AND QUANTITIES SPECIFIED ON THE PLANTING SCHEDULE. PLANT SUBSTITUTION SELECTION MUST BE APPROVED BY BIOLOGIST OR LANDSCAPE ARCHITECT PRIOR TO INSTALLATION.
- ALL PLANTS TO COMPLY WITH APPLICABLE REQUIREMENTS OF ANSI Z60.1 "AMERICAN STANDARD FOR NURSERY STOCK." LATEST EDITION. PUBLISHED BY THE AMERICAN NURSERY AND LANDSCAPE ASSOCIATION INC.
- PLANTS TO BE GROWN UNDER CLIMATIC CONDITIONS SIMILAR TO THOSE IN THE LOCALITY OF THE PROJECT FOR AT LEAST TWO (2) YEARS. USE HEALTHY NURSERY GROWN PLANTS, FREE OF DISEASE, INSECTS, AND PESTS. EGGS OR LARVAE, AND HAVE A WELL DEVELOPED ROOT SYSTEM.
- INSTALL PLANTS WITHIN ONE (1) WEEK OF PURCHASE. IF PLANTS ARE TO BE STORED AT THE SITE PRIOR TO PLANTING, IT IS THE CONTRACTOR'S RESPONSIBILITY TO ENSURE THEY ARE PROPERLY MAINTAINED, WATERED, AND REMAIN HEALTHY.
- PROCEED WITH PLANTING ONLY WHEN EXISTING AND FORECASTED WEATHER CONDITIONS PERMIT. SUBMIT TO THE LANDSCAPE ARCHITECT IN WRITING THE PROPOSED PLANTING SCHEDULE. OBTAIN APPROVAL OF PLANTING SCHEDULE FROM THE LANDSCAPE ARCHITECT PRIOR TO PERFORMING ANY

3. SEASONS FOR PLANTING:

FALL:

MARCH 31ST

SPRING: DECIDUOUS: APRIL 1 TO JUNE 15 APRIL 1 TO JUNE 15 FVFRGRFFN: PERENNIALS: APRIL 15 TO JUNE 1 GROUNDCOVERS: APRIL 15 TO JUNE 1 SEPTEMBER 15 TO NOVEMBER 15 DECIDUOUS:

SEPTEMBER 15 TO NOVEMBER 15 GROUNDCOVERS: LIVE STAKES: PLANTS WHILE DORMANT FROM DECEMBER 1ST THROUGH

EVERGREEN:

PERENNIALS:

PLANTING UNDER FROZEN CONDITIONS IN EITHER THE SPRING OR FALL WILL NOT BE PERMITTED. PLANTING BEFORE OR AFTER THE ABOVE REFERENCED PLANTING DATES WILL INCREASE THE LIKELIHOOD OF PLANT OR GRASS SEED ESTABLISHMENT FAILURE. ANY DEVIATION FROM THE ABOVE REFERENCED PLANTING DATES IS UNDERTAKEN AT SOLE RISK OF THE CONTRACTOR AND IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO PROVIDE ANY ADDITIONAL MAINTENANCE AND WATERING WHICH MAY BE REQUIRED TO ENSURE SATISFACTORY PLANT AND SEED ESTABLISHMENT.

SEPTEMBER 15 TO NOVEMBER 15

SEPTEMBER 15 TO NOVEMBER 15

-). FURNISH ONE YEAR MANUFACTURER WARRANTY FOR TREES, PLANTS, AND GROUND COVER AGAINST DEFECTS INCLUDING DEATH AND UNSATISFACTORY GROWTH, EXCEPT FOR DEFECTS RESULTING FROM LACK OF ADEQUATE MAINTENANCE, NEGLECT, OR ABUSE BY OWNER, OR ABNORMAL WEATHER CONDITIONS UNUSUAL FOR WARRANTY PERIOD. THE DATE OF FINAL ACCEPTANCE OF ALL COMPLETED PLANTING WORK ESTABLISHES THE END OF INSTALLATION AND INITIAL MAINTENANCE PERIOD AND THE COMMENCEMENT OF THE GUARANTEE PERIOD.
- 1. ALL TREES WITHIN 5'-0" OF WALKWAYS AND SIDEWALKS TO HAVE A 6'-8" STANDARD BRANCHING HEIGHT.
- 2. INSPECT ALL AREAS TO BE PLANTED OR SEEDED PRIOR TO STARTING ANY LANDSCAPE WORK. REPORT ANY DEFECTS SUCH AS INCORRECT GRADING, INCORRECT SUBGRADE ELEVATIONS OR DRAINAGE PROBLEMS, ETC. TO THE LANDSCAPE ARCHITECT AND ENGINEER PRIOR TO BEGINNING WORK. COMMENCEMENT OF WORK INDICATES ACCEPTANCE OF SUBGRADE AREAS TO BE PLANTED, AND THE LANDSCAPE CONTRACTOR ASSUMES RESPONSIBILITY FOR ALL LANDSCAPE WORK.
- B. PROVIDE PROPER PREPARATION OF ALL PROPOSED PLANTED AND SEEDED AREAS PER THE NOTES AND SPECIFICATIONS.
- 4. ALL PLANT LAYOUT AND ACTUAL PLANTING LOCATIONS ARE TO BE FIELD VERIFIED BY LANDSCAPE ARCHITECT PRIOR TO PLANTING. NOTIFY THE LANDSCAPE ARCHITECT AT A MINIMUM OF 48 HOURS IN
- 5. BALL AND BURLAP: REMOVE BURLAP AND WIRE BASKETS FROM TOPS OF BALLS AND FROM TOP HALF OF ROOTBALL AS INDICATED ON DRAWINGS. REMOVE PALLETS, IF ANY, BEFORE SETTING.
- 6. POTTED PLANTS: REMOVE THE PLANT FROM THE POT AND LOOSEN OR SCORE THE ROOTS BEFORE
- 7. PLUGS: PLANT UPRIGHT AND NOT AT AN ANGLE. DIG PLANTING HOLES LARGE ENOUGH AND DEEP ENOUGH TO ACCOMMODATE THE ENTIRE ROOT MASS. PLANT PLUGS WITH NO TWISTED OR BALLED ROOTS AND WITH NO ROOTS EXPOSED ABOVE THE GRADE LINE. HAND PACK THE SOIL AROUND THE ENTIRE PLUG ROOT MASS.
- 8. DIG THE THE PLANTING HOLE TO THE SAME DEPTH AS THE ROOT BALL AND TWO TO THREE TIMES WIDER. SCORE ALL SIDES OF THE HOLE, PLACE THE PLANT IN THE HOLE SO THE TOP OF ROOT BALL IS EVEN WITH SOIL SURFACE. FILL THE HOLE HALFWAY AND THEN ADD WATER ALLOWING IT TO SEEP INTO BACK FILLED MATERIAL. BE SURE TO REMOVE ALL AIR POCKETS FROM BACK FILLED SOIL. DO NOT SPREAD SOIL ON TOP OF THE ROOTBALL. IF SOIL IS EXTREMELY POOR, REPLACE BACK FILL WITH GOOD QUALITY TOP SOIL. AMEND THE SOIL, AS NECESSARY.
-). CREATE A 2" TO 4" BERM AROUND THE EDGE OF PLANTING HOLE WITH REMAINING SOIL TO RETAIN
- 20. REMOVE ALL PLANT TAGS AND FLAGS FROM THE PLANTS.

ADVANCE PRIOR TO SCHEDULING ANY FIELD INSPECTIONS.

PLANTING TO PROMOTE OUTWARDS ROOT GROWTH INTO THE SOIL.


- 1. MULCH ALL PLANTING BEDS AS INDICATED ON DRAWINGS. UNLESS NOTED OTHERWISE, ALL PLANTS TO RECEIVE 2-3 INCHES OF MULCH. DO NOT ADD MULCH TO BIORETENTION AND STORMWATER MANAGEMENT AREAS DO NOT PILE OR MOUND MULCH AROUND THE PLANT STEMS OR TRUNK.
- 22. TRIM BROKEN AND DEAD BRANCHES FROM TREES AND SHRUBS AFTER PLANTING. NEVER CUT A LEADER.

GENERAL SEEDING NOTES:


- SEND A REPRESENTATIVE SAMPLE OF THE TOPSOIL TO A TESTING LABORATORY FOR STANDARD SOIL ANALYSIS AS DESCRIBED IN THE SPECIFICATIONS. SUBMIT TO THE LANDSCAPE ARCHITECT AND ENGINEER TEST RESULTS WITH RECOMMENDED SOIL TREATMENTS TO PROMOTE PLANT AND GRASS GROWTH. CORRECT DEFICIENCIES IN THE LOAM AND STOCKPILED TOPSOIL AS DIRECTED BY THE TESTING AGENCY.
- ALL AREAS THAT ARE DISTURBED AND/OR GRADED DURING CONSTRUCTION ARE TO BE BROUGHT TO FINISHED GRADE WITH AT LEAST 4" MINIMUM DEPTH OF GOOD QUALITY LOAM AND SEEDED WITH A QUICK GERMINATING GRASS SEED SUCH AS NEW ENGLAND EROSION CONTROL RESTORATION MIX OR AS SPECIFIED ON THE PLANS.
- PRIOR TO THE PLACEMENT OF TOP SOIL, LOOSEN THE SUBGRADE OF ALL PROPOSED SEEDED AREAS TO A DEPTH OF 6" AND RAKE TO REMOVE STONES LARGER THAN 1 INCH, STICKS, ROOTS, RUBBISH AND OTHER EXTRANEOUS MATTER AND LEGALLY DISPOSE TO AN OFF SITE LOCATION.
- . DO NOT SPREAD TOPSOIL IF THE SUBGRADE IS FROZEN, EXCESSIVELY WET, COMPACTED OR NOT PROPERLY PREPARED PER THE NOTES AND SPECIFICATIONS.

WATERING NOTES:


- PROVIDE PROPER PLANT CARE, MAINTENANCE AND WATERING ON SITE UNTIL SUCH TIME AS THE LANDSCAPING IS ACCEPTED BY THE PROPERTY OWNER AS SATISFACTORY PER THE SPECIFICATIONS OR AS DETERMINED BY ANY WRITTEN AGREEMENTS BETWEEN THE CONTRACTOR AND PROPERTY OWNER.
- ESTABLISH AN APPROPRIATE WATERING SCHEDULE FOR ALL PLANT MATERIAL BASED UPON PLANT SPECIES REQUIREMENTS AND PROVIDE IN WRITING TO THE LANDSCAPE ARCHITECT AND OWNER FOR REVIEW AND APPROVAL, ADHERE TO THE APPROVED SCHEDULE UNTIL PLANTS ARE FULLY ESTABLISHED.
- AT A MINIMUM. THE NEWLY SEEDED AND/OR HYDROSEEDED LAWNS SHOULD BE WATERED 2-3 TIMES A DAY. SPECIAL CARE SHOULD BE TAKEN TO ENSURE THAT THE LAWN IS NOT SATURATED DURING WATERING. IF AN IRRIGATION SYSTEM IS NOT PROVIDED, A TEMPORARY IRRIGATION SYSTEM OR HANDHELD GARDEN HOSE SHALL BE USED FOR WATERING SEEDED AREAS. THE AREA MUST BE MAINTAINED CONSISTENTLY MOIST FOR THE BEST GERMINATION RESULTS. ADDITIONAL WATERING WILL BE REQUIRED IF PLANTING AND SEEDING OCCUR OUTSIDE OF THE RECOMMENDED PLANTING SEASONS.




CONTAINER PLANT ROOTBALL TREATMENT




PERENNIAL PLANTING **NOT TO SCALE**



LOAM AND SEED




SHRUB PLANTING NOT TO SCALE




SEE PLANS OR PLANTING SCHEDULE

PLANTING SPACING NOT TO SCALE



TREE PLANTING



1. ANCHOR BENCH TO CONCRETE PAD PER SPECIFICATIONS AND BENCH MANUFACTURER REQUIREMENTS.


BENCH MANUFACTURER: SEE SPECIFICATIONS 3. BENCH STYLE: SEE SPECIFICATIONS

BENCH CONCRETE PAD


BARNSTABLE MARSTONS MILLS VILLAGE CENTER IMPROVEMENTS

NO. SHEET 14 | 108


CONSTRUCTION DETAILS- DRAINAGE & LANDSCAPE **SHEET 10 OF 10**




GATEWAY NODE 2 DETAIL PLAN




BROOM FINISH CONCRETE








BARNSTABLE MARSTONS MILLS VILLAGE CENTER IMPROVEMENTS SHEET TOTAL SHEETS
17 109 **CONSTRUCTION PLAN** SHEET 3 OF 8 BEGIN PROP VGC - PROP VGC END PROP VGC TRANSITION PROP HMA DWY -\ REM TREE ¬ PROP CEM PROP CEM CONC DWY #10 - PROP CEM CONC DWY #11 CONC DWY #12 \(\square\) END PROP VGC - BEGIN PROP CEM CONC SW PROP HMA DWY **END PROP** PROP PVMT MATCH EXIST VGC -CEM CONC SW - BEGIN PROP VGC RECLAMATION -_ BEGIN PROP VGC BIT PARKING - PROP VGC TRANSITION BEGIN PROP VGC -END PROP VGC MATCH EXIST VGC BY PARKING PROP CEM END PROP VGC ~ CONC DWY #9 PROP CEM CONC WCR #4 \ REM TREE -PROP VGC REM TREE TRANSITION PROP VGC ¬ REM TREE -END PROP VGC -**ROUTE 149** R&R PLANTER PROP VGC


116 / TRANSITION TREE REM REM TREE TREE REM TREE END R&R VGC -REM TREE -PROTECTION -REM TREE REM TREE PROP CEM PROP CEM CONC SW CONC WCR #5 REM TREE -REM TREE | REM CONC STEPS | PROP VGC PROP CEM CONC TRANSITION -PROP TREE REM TREE + PROP STONE MASONRY WALL PROTECTION -(REFER TO MASSDOT DETAIL 302.2.0) PROP CEM-CONC WALK -PROP CEM CONC _WCR #7 → SCALE IN FEET















			S	STRUCTURE SCHEDULE		
	NAME	TYPE	RIM	INVERTS	STATION	OFFSET
\	CB 6.1	CATCH BASIN	36.57	12" INV OUT = 32.72 TO DMH 6.1	112+51.97	-10.00
	CB 6.2	CATCH BASIN	36.57	12" INV OUT = 33.55 TO DMH 6.1 8" INV OUT = 32.55 TO TREE TRENCH 2	112+51.97	10.00
(CB 7.1	CATCH BASIN	37.65	12" INV OUT = 33.70 TO RB 7.1 8" INV OUT = 33.60 TO TREE TRENCH 3	114+92.65	-10.00
	CB 7.2	CATCH BASIN	37.65	12" INV OUT = 34.60 TO RB 7.1 8" INV OUT = 33.60 TO TREE TRENCH 4	114+92.65	10.00
(RB 7.1	RECHARGE BASIN	37.82	12" INV IN = 33.66 FROM CB 7.1 12" INV IN = 34.54 FROM CB 7.2 12" INV OUT = 34.28 TO RB 7.2	114+96.77	-2.25
	RB 7.2	RECHARGE BASIN	37.85	12" INV IN = 34.28 FROM RB 7.1	115+07.26	-2.35

PIPE SCHEDULE						
FROM	TO	SIZE	MATERIAL	LENGTH	SLOPE	
CB 6.1	DMH 6.1	12"	HDPE	16'	0.50%)/1\
CB 6.2	TREE TRENCH 2	8"	HDPE	10'	0.54%	
CB 7.1	RB 7.1	12"	HDPE	4'	0.50%	b^{2}
CB 7.1	TREE TRENCH 3	8"	HDPE	$\left\langle \right\rangle$	0.41%	
CB 7.2	RB 7.1	12"	HDPE	8'	0.50%	
CB 7.2	TREE TRENCH 4	8"	HDPE	2'	1.30%	
RB 7.1	RB 7.2	12"	HDPE	4'	0.00%	

PIPE SCHEDULE						
FROM	TO	SIZE	MATERIAL	LENGTH	SLOPE	_
CB 6.1	DMH 6.1	12"	HDPE	16'	0.50%)/1\
CB 6.2	TREE TRENCH 2	8"	HDPE	10'	0.54%	
CB 7.1	RB 7.1	12"	HDPE	4'	0.50%	$)^{\angle 1\lambda}$
CB 7.1	TREE TRENCH 3	$\frac{1}{2}$	HDPE	1'	0.41%	
CB 7.2	RB 7.1	12"	HDPE	8'	0.50%	
CB 7.2	TREE TRENCH 4	8"	HDPE	2'	1.30%	
RB 7.1	RB 7.2	12"	HDPE	4'	0.00%	




BARNSTABLE MARSTONS MILLS VILLAGE CENTER IMPROVEMENTS


SHEET TOTAL SHEETS


25 108


DRAINAGE & UTILITY PLANS (3) SHEET 3 OF 8


REV#	DATE	
\triangle	11/28/18	
	_	















SHEET TOTAL SHEETS
31 109

PROFILE SHEET 1 OF 8 ROUTE 149

REV#	DATE	
\triangle	11/28/18	




MARSTONS MILLS VILLAGE CENTER IMPROVEMENTS

SHEET TOTAL SHEETS

32 109

PROFILE SHEET 2 OF 8 ROUTE 149

REV#	DATE	
\triangle	11/28/18	



BARNSTABLE


MARSTONS MILLS VILLAGE CENTER IMPROVEMENTS


SHEET TOTAL SHEETS

33 109

PROFILE SHEET 3 OF 8 ROUTE 149

REV#	DATE	
\triangle	11/28/18	






MARSTONS MILLS VILLAGE CENTER IMPROVEMENTS


SHEET TOTAL SHEETS


34 109


PROFILE SHEET 4 OF 8 ROUTE 149


REV#	DATE	
\triangle	11/28/18	






















	ROUTE 149 ALIGNMENT DATA									
N	IUMBER	START STATION	NORTHING	EASTING	CURVE DATA	LINE DATA	END STATION	NORTHING	EASTING	
	L6	114+53.76	240322.751	896996.152		N29° 41' 44"E 101.07'	115+54.84	240410.551	897046.224	

10.00'

10.00'

4.00'

14.00'

10.00'

3.00'

8.24'

4.45'

4.24' 33°37'06"


1.65' 18°44'37"


7.17' 71°18'35"


2.75' 85°00'17"


C305









































































LIGHT POLE PLACEMENT IN SIDEWALK DETAIL NOT TO SCALE


TYPICAL CONTROL CABINET SCHEMATIC WIRING DIAGRAM

BARNSTABLE MARSTONS MILLS VILLAGE CENTER IMPROVEMENTS SHEET TOTAL NO. SHEETS

LIGHTING DETAILS

65 109

REV#	DATE
\triangle	3/5/19



POWER SUPPLY NO	SYSTEM VOLTAGE	1 MAIN CIRCUIT BREAKER D.P.	2 CONTROL CONTACTOR	CIRCUIT	5 DISTRIBUTION BREAKER S.P.
1	120/240 V	60A	60A	A/B	20A
				C/D	20A
				E/F	20A

LEGEND:

- N NEUTRAL
- $L _1LINE 1$ $L - {}_{2}LINE 2$
- M MANUAL
- N AUTOMATIC
- SP SINGLE POST
- DP DOUBLE POST
- (1) MAIN CONTROL CABINET CIRCUIT BREAKS 60A, DP (10,000 AIC, MIN.)
- (2) CONTROL CONTACTOR 60A, DP (3) - PHOTOELECTRIC CELL (PLUG-IN TYPE)
- 4 SELECTOR SWITCH
- (5) DISTRIBUTION BREAKERS 20A, SP (10,000 AIC)
- 6 CONTROL CABINET (7) – 20A, SP BREAKER
- (8) LIGHTNING ARRESTER


PROVIDE A DISCONNECT BREAKER THAT IS SERVICE RATED, IN A SEPARATE NEMA 3R OR NEMA 4 ENCLOSURE AHEAD OF THE CONTROL CABINET AND MARKED "SUITABLE FOR USE AS SERVICE EQUIPMENT." PROVIDE AS A SEPARATE UNIT OUTSIDE THE MAIN ENCLOSURE WITH A LOCKABLE COVER AND NO EXTERNAL HANDLE. THE DISCONNECT MAY BE PROVIDED INTEGRAL TO THE CONTROL CABINET IF THE CABINET IS DEAD FRONT AND LABELED AS "SUITABLE FOR USE AS SERVICE EQUIPMENT."


ATTACH TO **GROUNDING LUG** LIGHT POLE -GRADE ¬ ANCHOR BASE COVER BOLT (TYP) TO JUNCTION BOX 1-1/2" PVC CONDUIT 4000 PSI CONCRETE - EXOTHERMIC WELD OR BRONZE CONNECTOR #4 AWG BARE COPPER GROUND -- GROUND ROD ½"x8'-0" 18" DIA

1. FOUNDATION DEPTH PER LIGHT POLE MANUFACTURER'S RECOMMENDATION. 2. ANCHOR BOLTS AND ANCHOR BOLT HARDWARE SIZED PER LIGHT POLE


> LIGHT POLE FOUNDATION NOT TO SCALE


MANUFACTURER'S RECOMMENDATION.








BARNSTABLE MARSTONS MILLS VILLAGE CENTER IMPROVEMENTS TRAFFIC SIGNS AND PAVEMENT MARKING PLAN SHEET 3 OF 8 JUED" SIGNS BIT PARKING / W3-1 SIGN (STOP AHEAD) BIT PARKING REM SIGNS /- RET PRIVATE SIGN PROP RRFB (SEE DETAIL ON SHEET 6) -PRIVATE SIGN — *
(SHELL STATION) R&R "MILLS" SIGN 🦴 ROUTE 149 DBYL PT +53.76 115 PROP RRFB (SEE DETAIL ON SHEET 6) PROP HANDICAP PARKING SYMBOL — WGL (TYP) – 4" WHITE 3' O.C. 1:1 SLOPE R7-8 -/ R7-8P SCALE IN FEET











BARNSTABLE
MARSTONS MILLS VILLAGE CENTER IMPROVEMENTS
SHEET TOTAL


TRAFFIC SIGN SUMMARY


TRAFFIC SIGN SUMMARY


IDENTIFI—	SIZE OF SIGN			TEXT DIMENSION	ONS (INCHES)	NUMBER COLOR OF			POST SIZE AND	UNIT	AREA IN
CATION NUMBER	WIDTH	HEIGHT	TEXT	LETTER VERTICAL ARROW RTE. MKR.		SIGNS	BACK- GROUND LEG	END BORDER	NUMBER REQUIRED	AREA (S.F.)	SQUARE FEET
R1-1	30"	30"	STOP	SEE 2009	9 MUTCD	3	SEE 2009	9 MUTCD	P5-1 3-REQ	6.25	18.75
R1-5	36"	36"	HERE TO			5			P5–1 5–REQ	9.00	45.00
R2-1	24"	30"	SPEED LIMIT 25			2			P5–1 2–REQ	5.00	10.00
R3-1	24"	24"				1			1-MOUNT W/ R1-1	4.00	4.00
R4-1	24"	30"	DO NOT PASS			1			P5–1 1–REQ	5.00	5.00
R4-11	30"	30"	MAY USE FULL LANE			5			P5–1 5–REQ	6.25	31.25
R7-8	12"	18"	RESERVED PARKING &			1			P5–1 1–REQ	1.50	1.50
R7-8P	12"	6"	VAN			1			1-MOUNT W/ R7-8	0.50	0.50
W3-1	30"	30"				2			P5-1 2-REQ	6.25	12.50
W3-3	30"	30"				1			P5–1 1–REQ	6.25	6.25
W11-2	30"	30"	(**)			15			P5–1 15–REQ	6.25	93.75
W11-8	30"	30"				1			P5-1 1-REQ	6.25	6.25
W13-1P	18"	18"	20 MPH			6			6-MOUNT W/ W17-1	2.25	13.50
W16-7P	24"	12"				11			11-MOUNT W/ W11-2	2.00	22.00


IDENTIFI— CATION NUMBER	SIZE OF SIGN			TEXT DIMENSIONS (INCHES)		NUMBER CO		COLOR	POST SIZE AND	UNIT	AREA IN	
	WIDTH	HEIGHT	TEXT	LETTER HEIGHT	VERTICAL SPACING	ARROW RTE. MKR.	SIGNS	BACK- GROUND	LEGEND BORDER	NUMBER	AREA (S.F.)	SQUARE FEET
W16-9P	24"	12"	AHEAD	SEE 2009 MUTCD		4	SEE 2009 MUTCD		4-MOUNT W/ W11-2	2.00	8.00	
W17-1	30"	30"	SPEED				6			P5-1 6-REQ	6.25	37.50
M1-5	24"	24"	28				3			P5-2 2-REQ P5-1 1-REQ	4.00	12.00
M1-5	30"	24"	149				4			P5–1 4–REQ	5.00	20.00
M2-1	21"	15"	JCT				1			1-MOUNT W/ M1-5 (28)	2.19	2.19
M3-1	24"	12"	NORTH				3			3-MOUNT W/ M1-5 (149)	2.00	6.00
M3-2	24"	12"	EAST				1			1-MOUNT W/ M1-5 (28)	2.00	2.00
M3-3	24"	12"	SOUTH				1			1-MOUNT W/ M1-5 (149)	2.00	2.00
M3-4	24"	12"	WEST				1			1-MOUNT W/ M1-5 (28)	2.00	2.00
M6-1R	21"	15"					1			1-MOUNT W/ M1-5 (28)	2.19	2.19
M6-1L	21"	15"					4			2-MOUNT W/ M1-5 (28) 2-MOUNT W/ RS-026	2.19	8.76
S3-1	36"	36"					1			P5–1 1–REQ	9.00	9.00
RS-026	24"	24"					2			P5–1 2–REQ	4.00	8.00
RS-026P	24"	12"	POST OFFICE				2			2-MOUNT W/ RS-026	2.00	4.00


TOTAL: 393.89 SF






















































































BARNSTABLE MARSTONS MILLS VILLAGE CENTER IMPROVEMENTS SHEET TOTAL SHEETS

105 109 CROSS SECTIONS - SHEET 12674 - Cross Sections - 29 OF 33 **MAIN STREET** REV# DATE 3/13/19 211+00

